# Ureolysis-induced calcium carbonate precipitation (UICP) in the presence of CO2-affected brine: a field demonstration

Catherine M. Kirkland, Arda Akyel, Randy Hiebert, Jay McCloskey, Jim Kirksey, Alfred B. Cunningham, Robin Gerlach, Lee Spangler, Adrienne J. Phillips

# Ureolysis-induced calcium carbonate precipitation (UICP) in the presence of CO$_2$-affected brine: a field demonstration

Catherine M. Kirkland[1,2*], Arda Akyel[1,3,] Randy Hiebert[4], Jay McCloskey[4], Jim Kirksey[5], Alfred B. Cunningham[1,2], Robin Gerlach[1,3], Lee Spangler[6], and Adrienne J. Phillips[1,2]

[1]Center for Biofilm Engineering, Montana State University, 366 Barnard Hall, Bozeman, MT 59717
[2]Department of Civil Engineering, Montana State University, 205 Cobleigh Hall, Bozeman, MT 59717
[3]Department of Chemical and Biological Engineering, Montana State University, 214 Roberts Hall, Bozeman, MT 59717
[4]Montana Emergent Technologies, 160 W Granite St, Butte, MT 59701
[5]Loudon Technical Services LLC, 1611 Loudon Heights Rd, Charleston, WV, 25314
[6]Energy Research Institute, Montana State University, P.O. Box 172465, Bozeman, MT 59717

## Highlights

- UICP in the presence of CO$_2$-affected brine reduced injectivity in a wellbore cement channel by an order of magnitude.
- Ultrasonic imaging logs conducted after UICP treatment showed additional solids behind the casing which extended at least 30 m (100 ft) above the injection zone.
- Urease enzyme from heat-treated microbial cultures was an effective catalyst for UICP reactions.

## Graphical Abstract



BEFORE
CO$_2$ flows through cracks in the concrete

AFTER
Biocement fills the cracks and prevents CO$_2$ flow

29    **Abstract**

30    Biomineralization is an emerging biotechnology for subsurface engineering applications like

31    remediating leaky wellbores.  The process relies on ureolysis to induce precipitation of calcium

32    carbonate in undesired flow paths.  In geologic storage of $CO_2$, there is a potential for leakage

33    and low pH conditions, thus, ureolysis-induced calcium carbonate precipitation (UICP) was

34    tested at field scale to seal a channel in the wellbore cement annulus in the presence of $CO_2$-

35    affected brine.  Conventional oil field methods were used to deliver UICP-promoting fluids

36    downhole to the treatment zone approximately 1000 feet (305 m) below ground surface (bgs).

37    Over 4 days, 242 L (64 gal) of heat-treated  *Sporosarcina pasteurii* cultures (22 bailers) and 329

38    L (87 gal) of urea – calcium chloride solution (30 bailers) were injected.  The UICP treatment

39    resulted in a 94% reduction of injectivity and ultrasonic well logging showed a noticeable

40    increase in the percentage of solids in the channel outside the casing, including more than 30 m

41    (100 ft) above the injection point.  Subsequent well logging 11 months after the field

42    demonstration showed that a significant portion of the new solids remained but the seal was

43    compromised following sustained pumping.  The results of this experiment suggest that UICP

44    can be promoted in the presence of $CO_2$-affected brine to seal leakage pathways. Additional

45    research is required to optimize long term seal integrity to ensure storage of $CO_2$ in geologic

46    carbon sequestration scenarios.

47    **Keywords**

48    Ureolysis-induced calcium carbonate precipitation, UICP, wellbore integrity, *Sporosarcina*

49    *pasteurii*, $CO_2$ sequestration

50

51    **1.  Introduction**

52    *1.1  Background*

53    Rising levels of $CO_2$ in the atmosphere must be reduced to achieve climate change

54    mitigation goals and limit the projected average global temperature increase [1].  A significant part

2

55    of this effort is carbon capture and sequestration (CCS) wherein $CO_2$ captured from point

56    sources like coal-fired power plants or chemical processing facilities is compressed to a

57    supercritical state and injected into subsurface storage reservoirs for sequestration on geologic

58    time scales [2].  Maintaining wellbore integrity is essential to ensuring that sequestered $CO_2$ stays

59    trapped in subsurface reservoirs and is not re-emitted to the atmosphere via leakage pathways

60    in the near wellbore environment.  Current state of the art for mitigating leaky wellbores [3] where

61    conventional squeeze cementing is not appropriate includes use of fine cement, resins [4], and

62    nanomaterials [5, 6].  Many of these methods are appropriate for leakage pathways on the order of

63    100 µm or larger but cannot penetrate micro-scale cracks due to the high viscosity of the sealing

64    agents.  Biocement, produced during the process of ureolysis-induced calcium carbonate

65    precipitation (UICP), is emerging as a contender to aid in wellbore sealing applications where

66    more conventional methods are unsuccessful or inappropriate [7-9].  In this study, we report on a

67    field study which applied UICP in the presence of $CO_2$-affected brine to repair compromised

68    cement in a test well.

69

70    *1.2  UICP Fundamentals*

71        It has long been known that enzyme catalysis can be harnessed to hydrolyze urea and

72    precipitate calcium carbonate [10].  The enzyme urease is widespread in nature and can be found

73    in microbes like bacteria and algae, as well as in fungi and plants [11].  Ureolysis results in a pH

74    increase and produces bicarbonate ($HCO_3^-$) and carbonate ($CO_3^{2-}$) ions.  When calcium ($Ca^{2+}$)

75    activity is sufficient to exceed saturation conditions, calcium carbonate ($CaCO_3$) precipitation

76    can occur [Eqn. 1].

77

78    $$CO(NH_2)_2 + 2H_2O + Ca^{2+} \rightarrow 2NH_4^+ + CaCO_3\,(s) \qquad [1]$$

79

3

80    During ureolysis-induced calcium carbonate precipitation (UICP), ureolytic bacterial cultures

81    can serve as both the source of the urease enzyme and can form a biofilm matrix on surfaces.

82    Additionally, the biofilm is believed to provide nucleation sites for precipitation to initiate [12-14].

83    Over multiple injections of ureolytic cultures and UICP-promoting media, the $CaCO_3$ mineral

84    thickens, bridges pore throats and fractures, fills voids, and ultimately seals flow pathways [15].

85

86    *1.3 Project overview*

87    The primary goal of this project was to assess the ability of UICP to form a bio-cement seal

88    in the near wellbore environment in the presence of $CO_2$-affected brine. Dissolved $CO_2$ reduces

89    the brine pH and the fraction of $CO_3^{2-}$ ions in solution, thereby potentially making $CaCO_3$

90    precipitation less likely and instead favoring dissolution of carbonate minerals.  Since UICP has

91    been successful in sealing leaky wellbores in the oil and gas industry [7, 8], it is important to

92    assess the extent to which the process could be applied in the context of $CO_2$ sequestration

93    where exposure to $CO_2$-affected brine is possible.

94    A secondary goal of this UICP field demonstration was to evaluate the extent to which heat-

95    treated microbial cultures can effectively seal undesired flow pathways.  The ureolytic

96    bacterium, *Sporosarcina pasteurii*, was the source of the urease enzyme in this study but

97    cultures were briefly heat-treated prior to injection to inactivate the microbes while preserving

98    enzyme activity. The use of heat-treated cells with intact enzyme activity may offer a viable

99    alternative in situations where injection of live cells is problematic from either a logistical or

100   regulatory standpoint. The heat treatment also mimics conditions in the deeper subsurface

101   where elevated temperature would impact cell survival.

102   The field demonstration of UICP sealing in the presence of $CO_2$-affected brine was

103   conducted in a 24.4 cm (9.625 inch) outer-diameter cased test well at the William Crawford

104   Gorgas Electric Generating Plant (Alabama Power, Southern Company) near Parrish, Alabama,

105   USA, hereafter referred to as "Gorgas". The well was drilled to a depth of 1498 m by the U.S.

4

106    Department of Energy to assess the potential for geologic carbon sequestration. The target

107    formation(s), however, proved to be unfavorable for $CO_2$ storage so the well has been used

108    instead for research purposes. Previous field tests, which used live microbial cultures as the

109    source of the urease enzyme, focused on sealing a hydraulic fracture in a sandstone formation

110    340 m (1115 ft) below ground surface (bgs) [16] and sealing a channel in the well cement 310 m

111    (1017 ft) bgs [9]. Additional details about the well are available in Phillips *et al*. (2016)[16] and in

112    Section 2.1 below.



113

114    **Figure 1.** The experimental timeline of the field demonstration. Samples were collected from

115    the downhole injection zone four times (red arrows). Injections of 5% HCl and $NaHCO_3$ were

116    used to generate $CO_2$ in the wellbore annular defect. Ultrasonic imaging (USIT) logs were

117    collected twice during the field demonstration (Day 1, 6) to image the materials in the wellbore

118    annulus, before and after injections of UICP-promoting fluids. Biomineralization in the annular

119    cement channel was monitored during UICP injections using pressure and flow rate

120    measurements. A third USIT log was acquired 11 months after the field work ended (Day 327).

121

122

123        Figure 1 summarizes the types of activities performed and order of events during the current

124    field demonstration. Detailed descriptions of each activity follow in later sections. Water

125    samples were collected four times over the course of the study (red arrows) to characterize

5

126 downhole geochemical and microbiological conditions. (This data will be reported elsewhere by

127 project collaborators.)  Because flow behind the casing at the study depth, 310 m (1017 ft) bgs,

128 had been effectively minimized with UICP during the second field demonstration [9], acid

129 injections were used first to dissolve the calcium carbonate biomineral and establish a flow path

130 in the wellbore cement annulus.  Once a channel was formed, $CO_2$ was produced behind the

131 casing and injections of UICP-promoting fluids began. Throughout injection, pressure and flow

132 rate were monitored to assess changes in injectivity, defined here as the flow rate divided by the

133 injection pressure.  Injectivity serves as a proxy for permeability or transmissivity since flow path

134 geometry through the compromised cement is unknown.  Decreasing injectivity is an indication

135 of mineral formation in the channel[15, 17-20].  In addition, ultrasonic imaging logs were conducted

136 twice to assess the extent of mineral formation behind the casing due to UICP.  The field

137 demonstration was ended when the injection pump's maximum pressure and minimum flow rate

138 were reached.  A subsequent seal integrity check was performed approximately 11 months (327

139 days) after the field demonstration ended and additional ultrasonic well logging was performed.

140 Following the seal integrity check, the well was plugged and abandoned in accordance with

141 regulatory requirements.

142

143 **2.  Materials and Methods**

144 *2.1  Well preparation and experimental design*

145     The current work is the research team's third field demonstration of ureolysis-induced

146 calcium carbonate precipitation in the Gorgas well.  This field demonstration was conducted at

147 310 m (1017 ft) bgs, the same depth as the previous well cement sealing demonstration where

148 the temperature is approximately 15°C.  The static water level in the well was approximately 10

149 m (30 ft) bgs at the beginning of the demonstration.  The three sidewall perforations in the steel

150 casing drilled during the previous study at 310.0, 310.3, and 310.9 m (1017, 1018 and 1020

151 feet) bgs were again used to access the cement annulus [9].  The 7.3 cm (2-7/8-inch) steel

6

152    injection tubing string extended from the surface to a depth of 312.7 m (1026 ft) bgs, including a

153    1 m (3 ft) perforated pup joint ending in a collar stop at 311.6 m (1022 ft).  A bull plug closed off

154    the end of the tubing at 312.8 m (1026 ft) bgs.  The target  injection zone was isolated by a

155    packer above the casing perforations and a bridge plug below.  The packer was placed between

156    the tubing string and casing at a depth of 296.6 m (973 ft) bgs.  A 24.4 cm (9-5/8-inch) cast iron

157    bridge plug was set at a depth of 316 m (1037 ft) bgs and was topped with 1.5 m (5 ft) of

158    cement to prevent fluid from migrating down the casing below the injection point.  An 11 L (2.9

159    gal) slickline dump bailer was used to deliver fluids to the subsurface. Fluids were pumped into

160    the bailer at the wellhead with transfer pumps and hoses dedicated to each fluid type. The

161    bottom of the bailer was fitted with a glass disk that shattered upon impact with the collar stop at

162    the target injection zone.  Fresh water pumped down the tubing string after impact flushed the

163    fluids from the bailer, tubing string, and wellbore through the sidewall perforations and into the

164    cement channel behind the casing.  Bailer delivery downhole and return to the surface took

165    approximately 20 minutes.

166    The initial injectivity [L/min*MPa (gal/min*psi)] of the system was obtained by monitoring the

167    wellhead pressure during an initial injection test of water down the tubing string. Injectivity was

168    low initially since the prior field demonstration [9] had sealed the flow channel behind the casing

169    in the same injection zone.

170    After the initial injection test, 3 bailers (33 L) of 5% HCl were delivered downhole to expand

171    the flow path in the cement by dissolving biomineral formed during the previous field

172    demonstration in the well.    Following the expansion of a flow path in the cement, three bailers

173    (33L) each of 5% HCl and 100 g/L $NaHCO_3$ were injected in an alternating fashion to produce

174    $CO_2$ in the near wellbore environment according to Eqn. 2.

175

176                $HCl + NaHCO_3 \rightarrow Na^+ + Cl^- + H_2O + CO_2(g)$                Eqn. 2

177


7

178  Direct $CO_2$ injection would have required a rigorous EPA Class VI injection permitting review

179  process, which was not feasible during the timeframe of this project.  The amount of HCl (1.26

180  kg or 34.8 mol) and $NaHCO_3$ (3.3 kg or 39.2 mol) injected for $CO_2$ production have a theoretical

181  $CO_2$ production of approximately 35 mol, assuming that all the reactants were consumed in the

182  intended reaction.  The HCl injections to open a flow path in the wellbore annulus could have

183  produced additional $CO_2$, depending on the extent of the reaction with calcium carbonate

184  produced during the previous field demonstration.

185      Following $CO_2$ production, injections of UICP-promoting fluids began. For the first 2 days of

186  injecting UICP-promoting fluids, one bailer of heat-treated cells was followed by two bailers of

187  urea – calcium solution.  Starting the end of the second day, the bailer contents alternated

188  between heat-treated cells and urea – calcium solution.

189

190  *2.2  Well characterization – USIT logs and sampling*

191      An ultrasonic imaging (USIT) log was collected twice during the field demonstration using an

192  Isolation Scanner (Schlumberger) which produces a Solid-Liquid-Gas (SLG) map of the

193  wellbore annulus via measurement of the cement impedance and flexural wave attenuation. The

194  first USIT log was recorded after establishing a flow path with acid injection but before $CO_2$

195  production.  The second USIT log was collected at the end of the field demonstration after 4

196  days of injecting UICP-promoting fluids. Another USIT log was acquired approximately 11

197  months (327 days) after the end of the field demonstration prior to plugging and abandoning the

198  Gorgas well.  Image analysis using ImageJ software (v1.8.0_172) was performed to quantify the

199  solids detected behind the casing in each USIT log.  The area of the image occupied by tan

200  pixels, which represent solids, were measured after applying a color threshold to the image

201  histogram. Solids correspond to hue values between 17 – 50  on the 0 – 255 scale.  The full 0 –

202  255 range was applied for both saturation and brightness.

203    At the end of the field demonstration, samples of precipitates were scraped from the

204    injection tubing and 'sludge' from the well sump and bottom plug was collected for analysis.

205    These samples were subjected to X-ray diffraction (XRD) analysis to characterize the mineral

206    composition. Samples were dried and pulverized then deposited onto a glass slide coated with a

207    thin layer of petroleum jelly and analyzed with a Scintag X1 Powder X-ray diffractometer

208    equipped with a copper (Cu) k-alpha X-ray source housed at the Imaging and Chemical

209    Analysis Laboratory (ICAL) at Montana State University.

210

211    2.3  *UICP-promoting fluids*

212    Microbial cultures were started by inoculating 1L 18.5 g/L BHI media (Becton Dickinson,

213    Franklin Lakes, NJ) plus 20 g/L urea (Fisher Scientific) with 10 mL ($4.4 \times 10^6$ CFU/mL) of frozen

214    stock of *Sporosarcina pasteurii* (ATCC® 11859™).  After approximately 16 hours, the 1L culture

215    was transferred to 45.4 L (12 gal) yeast extract medium (15.5 g/L yeast extract, 24 g/L urea

216    (Dyno Nobel, Inc, Deer Island OR), 1 g/L $NH_4Cl$).  The 45.4 L cultures were grown at 30°C for

217    approximately 24 hours in 56.8-L (15-gal) conical bottom reactors equipped with aeration,

218    temperature control, ventilation, and recirculation as described in Kirkland *et al*. (2020) [7] and

219    shown in Figure 2.



220

9

221     **Figure 2.** Heat-treatment system developed in the custom MSU mobile laboratory received flow
222     from 24-hr cultures grown in the bioreactors (left). The 60°C heat-treatment tank (left) was
223     wrapped in insulation to reduce heat losses.  The cooling tank, located outside of the trailer,
224     contained water below 30°C. Cultures were pumped through stainless steel coils in both the
225     heating and cooling tanks.

226

227         After approximately 24 hours of growth in the conical bottom reactors, the *S. pasteurii*
228     cultures were combined in a holding tank from which they were pumped with a peristaltic pump
229     into the heat-treatment system (Figure 2). Microbes were heat-treated as they flowed through
230     coiled tubing suspended in reactor heated to 60°C.  During the first two days of the field
231     demonstration, a 15.24 m (50-ft), 1.27 cm (1/2-inch) OD 316 stainless steel (SS) coil was used.
232     For the remainder of the experiment, a second coil was added in series (15.24 m (50-ft), 0.95
233     cm (3/8-inch) OD 316 SS) to allow for higher flowrates while maintaining adequate residence
234     time in the 60°C reactor (i.e. 8-13 minutes). Temperature was maintained at 60°C in the hot
235     water bath with immersion heaters and insulation was wrapped around the tank to reduce heat
236     loss.  Heat-treated cells were cooled using a 15.24 m (50-ft), 0.95 cm (3/8-inch) OD 316 SS coil
237     submerged in a < 30°C water bath to protect the urease enzyme from inactivation due to
238     prolonged exposure to elevated temperature (Figure 2) [21]. Cooled cultures were stored in a
239     holding tank at ambient temperature until they were delivered into the well.
240         Microbial cultures were sampled each day before and after heat treatment.  Population
241     analysis was performed using the drop plate method [22] to count colony forming units (CFU).
242     The detection limit was $1 \times 10^3$ CFU/mL.  Before filling the bailer for an injection, the heat-
243     treated cultures were also sampled for pH, electrical conductivity (EC), urea analysis with the
244     Jung Assay [23], and optical density.  Optical density ($OD_{600}$) was measured in triplicate to monitor
245     growth in the reactors from 200 μL samples in a 96-well plate at 600 nm using an Infinite F50
246     plate reader (Tecan, Switzerland). $OD_{600}$ of the fresh YE medium blank was 0.05 ± 0.002.

247     Urea-calcium solution (U+C) was prepared daily with 72 g/L urea and 124 g/L $CaCl_2$

248     (Peladow, Occidental Chemical Corp., Dallas, TX) in a 132-L (35-gal) tank.  The U+C solution

249     was mixed with a drill-powered mixer and sampled for pH, urea, and $Ca^{2+}$ analyses.

250

251     *2.4  Batch studies – Ureolytic activity*

252     The ureolytic activity of heat-treated cultures was compared to that of actively growing

253     microbial cultures using EC [mS/cm] measurements. Due to the production of $NH_4^+$ ions during

254     ureolysis (Eqn. 1), increases in EC over time can be used as a proxy to compare ureolysis rates

255     between samples [24].  Ten mL of 20 g/L urea (Fisher Scientific) solution was added to 10 mL

256     samples of both actively growing *S. pasteurii* cultures and heat-treated cultures in 50 mL conical

257     tubes.  Mixtures were vortexed initially and immediately prior to EC measurements.  EC

258     measurements were performed every 30 minutes for 3 hours.

259

260     *3.* **Results**

261     *3.1  Reduced Injectivity*

262     Wellhead pressure and pumping flow rate were monitored and recorded as water was

263     injected to push each bailer of fluids into the wellbore channel.  Figure 3 shows the injectivity of

264     each bailer delivery as a function of total injection volume.  Approximately 242 L (64 gal) of

265     heat-treated microbial cultures (22 bailers) and 329 L (87 gal) of U+C media (30 bailers) were

266     injected over 4 days.  The UICP treatment resulted in an order-of-magnitude reduction of

267     injectivity in the channel (Figure 3) which is indicative of biomineral formation in flow pathways

268     outside the well casing. The preliminary low injectivity of 0.76 L/min*MPa ($1.38 \times 10^{-4}$ gpm/psi)

269     measured during initial freshwater injection increased to 9.33 L/min*MPa ($1.73 \times 10^{-3}$ gpm/psi)

270     after the injection of HCl to open a flow path (Figure 3).  The highest injectivity during the

271     experiment occurred during the injection of HCl and $NaHCO_3$ to produce $CO_2$ when the flow rate

272     was 8.33 L/min (2.2 gpm) at 0.49 MPa (708 psi) for an injectivity of 17.1 L/min*MPa ($3.11 \times 10^{-3}$

11

273    gpm/psi).  After $CO_2$ production but before UICP treatment, the channel conveyed 4.9 L/min at

274    0.49 MPa (1.3 gpm at 712 psi), for an injectivity of 10.0 L/min*MPa ($1.83x10^{-3}$ gpm/psi).  During

275    UICP treatment, injectivity was stable for two days before decreasing rapidly.  On the third day

276    after beginning UICP injections and at a cumulative injection volume of approximately 1740 L

277    (460 gal), injectivity decreased significantly before leveling off, then decreasing again in a 'stair-

278    step' pattern (Figure 3).  The final flow-pressure relationship at the end of the field

279    demonstration were 0.757 L/min at 0.761 MPa (0.2 gpm at 1104 psi) which equates to an

280    injectivity of 0.99 L/min*MPa ($1.81x10^{-4}$ gpm/psi).  An injection test 11 months later produced an

281    injectivity of 2.56 L/min*MPa ($4.67x10^{-4}$ gpm/psi) which increased to 8.62 L/min*MPa ($1.57x10^{-3}$

282    gpm/psi) following sustained pumping.  Red arrows in Figure 3 indicate when USIT logs were

283    acquired.

284

285



286

287

288    **Figure 3.**  Injections of 5% HCl were used to open a flow path behind the well casing and then

289    injections of 5% HCl and $NaHCO_3$ were used to generate $CO_2$ in the annular cement channel.

290    Subsequent injections of UICP-promoting fluids reduced the injectivity by an order-of-magnitude

12

291     over days 3-6.  Fresh water injections (Δ), 5% HCl injections (•), HCl/NaHCO$_3$ injections to

292     produce $CO_2$ (■), UICP-promoting injections (◊), and pre-abandonment injection test (x).  Red

293     arrows indicate USIT logs. Vertical lines indicate days along secondary x-axis; time scale is not

294     linear.

295

296     *3.2  USIT logs*

297         The Gorgas well was logged ultrasonically twice during the field demonstration and again 11

298     months later (Figure 3, red arrows).  USIT logs (Figure 4) show a 2D projection of the materials

299     detected immediately behind the casing (right panel of each log) as a function of depth in the

300     borehole (left panel of each log).  In the first USIT log acquired during the current field work

301     (left), the acid treatment appears to have expanded a channel outside the casing (black oval)

302     relative to the final USIT log recorded at the end of the prior wellbore sealing demonstration[9].

303     The corresponding injectivity was 9.33 L/min*MPa (1.70x10$^{-3}$ gpm/psi) (Figure 3).  After UICP

304     treatment in the presence of $CO_2$-affected brine (middle), there was a noticeable increase in the

305     presence of solids in the channel in the region of the side wall perforations 300 – 310 m (990-

306     1019 ft) bgs and more than 30 m (100 ft) above the injection point (red ovals).  Compared to the

307     initial USIT log, the post-UICP log shows a 58% increase in the image area occupied by solids

308     behind the casing for the depth interval shown in Figure 4.  The USIT log recorded  on Day 327,

309     approximately 11 months after the end of the field work (Figure 4, right)  prior to plugging and

310     abandoning the well, shows that significant solids remain despite the loss of solids relative to

311     the Post-UICP log.  The image area occupied by solids measured in this last USIT log is 30%

312     greater than in the initial USIT log.  The relative abundance of solids in the well-log images is

313     consistent with injectivity values recorded over the course of the fieldwork.  Higher proportions

314     of solids correspond to lower injectivity and vice versa.

315

13

**INITIAL**  **POST-UICP**  **11 MO. LATER**

316

**Figure 4.** USIT logs showing a 2D projection of the materials immediately outside the casing before and after UICP treatment, where tan=solids, blue=liquid and red=gas detected. Fluids were able to access the cement defect/channel in three potential locations (990, 1004, 1017-1019 feet below ground surface) indicated by red arrows due to previously drilled sidewall perforations. Before production of $CO_2$ and UICP treatment, a channel was observed in the solid material detected behind the casing (black oval on left panel). After UICP treatment a significant increase in the amount of solid was observed (red ovals, middle panel). A follow-up USIT log 11 months later (Day 327, right panel) shows that significant solids remained in the location despite some loss.

*3.3 Sample analysis*

XRD analysis of mineral samples collected from the injection tubing show that the mineral was 74.9% calcite ($CaCO_3$), 22.2% vaterite ($CaCO_3$), and 2.9% quartz ($SiO_2$). A sample from the well sump, which is located between the collar stop and the bottom plug, was 67.2% quartz and

14

331    32.8% magnetite ($Fe_3O_4$). Two samples of solids collected from the bottom plug were

332    predominantly iron species, magnetite and iron (III) oxide hydroxide ($FeO(OH)$)), with quartz

333    comprising 33% and 25% of each sample, respectively.

334

335    *3.4 Heat treatment of microbial cultures*

336    *Sporosarcina pasteurii* cultures were grown to an average concentration of $2.5 \times 10^8$ CFU/mL

337    in the mobile laboratory conical bottom bio-reactors prior to heat-treatment. No colonies of

338    heat-treated cells were observed above the detection limit on the agar plates after 24 hours.

339    Batch studies to compare the ureolytic activity of growing vs. heat-treated cultures showed

340    larger increases in EC in the heat-treated cultures than in the growing cultures. EC increased

341    on average 41% more in heat-treated samples, with a standard deviation of 23 percentage

342    points. Excluding Day 2 data, which was an outlier, EC increased 51% more in heat-treated

343    cultures (St.dev = 7 percentage points).

344

345    **4. Discussion**

346    Presence of $CO_2$ in the wellbore annulus does not appear to have impeded calcium

347    carbonate mineral formation as evidenced by the order-of-magnitude reduction in injectivity and

348    the increased solids detected in the post-UICP treatment USIT log. These findings corroborate

349    previous studies which have found that UICP can occur in the presence of $CO_2$[25, 26].The 'stair

350    step' behavior of injectivity reduction is characteristic of UICP sealing in channels or fractures,

351    where substantial mineral precipitation is often necessary before measurable flow restriction

352    occurs. In these channel-type systems, mineral formation must reach a critical threshold before

353    the ratio of pressure and flow measurements, or injectivity, registers significant change. Once

354    the flow path is partially restricted, however, conditions are favorable at that location for

355    additional mineral to form and injectivity decreases dramatically over a relatively short time

356    frame [15]. In this field demonstration, this pattern appears to repeat three times (Figure 3), with

15

357 the decreases occurring the morning of the third day of injecting UICP-promoting fluids (at a

358 cumulative injection volume of approximately 1741 L (460 gal)), the morning of the fourth day

359 (approximately 2214 L (585 gal)) and at the final bailer injection (2362 L (624 gal)). Similar

360 behavior has been observed in other studies monitoring sealing of channels with UICP [15, 16, 18-20,

361 27, 28] though some report only a single 'stair step' before the channel sealed. The results

362 obtained during this field demonstration suggest that when a preferred flow path sealed due to

363 UICP, the reactants were re-routed through another path in the wellbore annulus until that one

364 also sealed, and so on. This sealing behavior is in contrast to that reported where the seal

365 formed within a higher permeability sandstone rock matrix in a waterflood injection well [7, 8] or

366 within a laboratory bio-reactor sand pack [29]. In these cases, mineralization and sealing of the

367 pore spaces proceeded gradually over time in a nearly linear fashion. In systems where

368 permeability is more evenly distributed, each pore that fills or is blocked with bio-mineral

369 fractionally reduces the injectivity of the system until few pathways remain open[30].

370 The XRD data from the tubing string samples confirms that calcium carbonate precipitation

371 occurred downhole following the injection of UICP-promoting fluids. The fact that calcium

372 carbonate polymorphs were not detected in the sump and bottom plug suggests that the

373 mineralizing fluids were successfully transported out of the wellbore and that the precipitation

374 reactions proceeded within the cement channel as intended. The presence of iron species in

375 the well sump and bottom plug is to be expected. Raising and lowering the bailer repeatedly

376 within the steel tubing string, injection of acid to open a flow path, and injection of acid and

377 $NaHCO_3$ to form $CO_2$ likely contributed to the accumulation of iron species at the bottom of the

378 tubing string.

379 Extended exposure to elevated temperatures (greater than 65°C) is known to inactivate the

380 urease enzyme which could inhibit ureolysis-induced mineral precipitation [21, 31]. In this study,

381 however, EC data points to higher rates of ureolysis in the heat-treated cultures. This apparent

382 contradiction is related to the temperature, 60°C, and duration of exposure the microbial

16

383    cultures experienced which was limited to 8 – 13 minutes.  The goal was to inactivate the cell

384    without inactivating the enzyme.  Thus, one explanation for the observed increase in ureolytic

385    activity in heat-treated cultures relates to the integrity of the cell wall following heat stress.  A

386    partial breakdown of bacterial cell walls could enhance transport of urea into or urease enzyme

387    out of the cell, thereby increasing urea hydrolysis rates. In the case of the live cells, transport of

388    urea into the cells (or urease out of the cells) is recognized as a rate-limiting step in urea

389    hydrolysis [32, 33].

390        The USIT logs acquired during this project show both the potential of the UICP

391    biotechnology to seal leakage pathways in wellbores as well as some remaining questions

392    related to seal durability.  The Post-UICP USIT log shows extensive solids precipitation not only

393    in the immediate vicinity of the injection, but also far above.  Due to the presence of a bridge

394    plug in the casing, it was not possible to observe the extent of mineral formation below the

395    injection point though there is no reason to assume mineral could not have formed there.

396        The available data regarding the durability of UICP mineral seals in this well is mixed and

397    highlights the need for additional research on the topic.  First, the preliminary water injection,

398    shown as the first data point in Figure 3, yielded a low initial injectivity of 0.76 L/min*MPa

399    ($1.38 \times 10^{-4}$ gpm/psi) and indicates that the seal produced during the previous demonstration of

400    UICP in the well [9] remained in place during the 18 months between field demonstrations.

401    Moreover, our small business team members have successfully deployed UICP to seal leakage

402    pathways in 11 commercial oil and gas wells in Colorado and Wyoming [7] with no additional

403    treatment required to satisfy regulatory standards for operation or abandonment.  Four of these

404    wells in the Denver-Julesburg Basin of Colorado were horizontal production wells in the

405    Niobrara formation experiencing sustained casing pressure ranging from 80 psi (0.55 MPa) to

406    899 psi (6.2 MPa) prior to UICP treatment.  Immediately after treatment, casing pressure in all

407    wells was reduced to 0 psi (0 MPa).  After six months in operation following UICP treatment, two

408    of the wells produced casing pressure readings of 5 psi (0.03 MPa) and 2 psi (0.01 MPa)

409   (unpublished data), which is well below the regulatory value of 50 psi (0.34 MPa) that triggers

410   remedial action.  The remaining two wells, which had initially yielded the highest sustained

411   casing pressures of 395 psi (2.7 MPa) and 899 psi (6.2 MPa), remained at 0 psi (unpublished

412   data).  These findings from the Gorgas well and commercial production wells provide evidence

413   that the calcium carbonate biomineral seal can be durable over a timeframe of months to years.

414     At the same time, the USIT log acquired prior to abandoning the well (Figure 4, right) shows

415   a loss of solids relative to the Post-UICP USIT log acquired at the end of the field demonstration

416   (Figure 4, middle).  Injectivity data suggests that the seal was further compromised following

417   sustained pumping during the subsequent injection test.  There are several possible

418   explanations for this observed behavior.  First, residual $CO_2$ in the near wellbore environment

419   may have produced low-pH conditions favorable for calcium carbonate dissolution.  Second,

420   heat-treatment of cells may have altered the microbial phenotype such that cells did not firmly

421   attach to surfaces as a biofilm prior to mineralizing.  It is not possible, given the available data

422   from this field demonstration, to say with certainty which of these scenarios, if either, caused the

423   loss of solids after the field demonstration ended.  Two points, however, are worth noting.

424   First, acidic pH conditions (e.g. < pH 7) are known to promote calcium carbonate dissolution

425   wherein the rate of dissolution depends on complex geochemical and hydrodynamic factors

426   related to fluid saturation states at the solid-liquid interface[25].  The surface area of the mineral

427   seal exposed to wellbore fluid is of critical importance.  We hypothesize that the amount of

428   calcium carbonate that dissolves due to low pH conditions is proportional to the exposed

429   surface area.  Therefore, the seal in Figure 4, which has flow pathways around the well

430   circumference and exposed surface area distributed over several meters along the wellbore

431   axis, would be expected to be impacted more by acidic conditions than a similar aperture seal

432   with fewer flow paths and less exposed surface area. The relatively uniform dissolution of

433   exposed seal edges, apparent in the two USIT logs, should be noted.


18

434    Second, despite exhibiting higher ureolysis rates than live cells, the heat-treated *S. pasteurii*

435    cultures do not appear to have produced as robust a seal as live cells have done in previous

436    demonstrations [9]. Ma *et al.* [34] indicate that intact cell structure promotes nucleation of mineral

437    during UICP. Secchi *et al.* [35] found preferential attachment of elongated, motile cells (like

438    *S.pasteurii*) on the downstream side of surface roughness under moderate hydrodynamic

439    conditions. Heat-treatment would be expected to modify both of these phenotypic

440    characteristics – cell shape and motility – via damage to the cell membrane, thereby decreasing

441    the capture efficiency or attachment of cells to the surfaces in the wellbore and by reducing the

442    potential of the cell to act as a nucleation site. Heat-treated cells would be more likely to

443    behave instead as passive particles in the flow where they would be intercepted by surfaces on

444    the upstream side of wellbore annulus surface roughness [35]. This 'passive particle' behavior

445    may be useful in explaining the formation of mineral so far above the injection zone. Heat-

446    treated cells may have been carried in the flow up the well casing beyond the injection point

447    until they intercepted a surface due, in part, to cell lysis and other phenotypic changes.

448    Further numerical simulations [36, 37] and validation of these hypotheses in the lab could

449    elucidate the mechanisms that promote a durable seal and advance the process to develop

450    deployable microbial cultures for large-scale adoption of the biotechnology in the field [38].

451

452    **5. Conclusions**

453    The presence of $CO_2$ did not impede mineral formation during the field demonstration as

454    evidenced by the reduction in injectivity observed during UICP treatment as well as the

455    additional solids present in the post-treatment USIT log. Additionally, urease enzyme from heat-

456    treated microbial cultures was an effective catalyst for the UICP reactions and higher ureolysis

457    rates were observed in the heat-treated cultures than in live cultures, perhaps due to cell lysis.

458    At the same time, the seal formed in the wellbore annulus in this field demonstration was less

459    robust than a previous seal produced by UICP in the same well without the presence of $CO_2$-

19

460 affected brine and using live microbes.  The results of this experiment suggest that UICP can be

461 promoted in the presence of $CO_2$ impacted brine to seal leakage pathways and may be effective

462 to ensure storage of $CO_2$ in geologic carbon sequestration scenarios.  Further research is

463 needed to study the durability of the seal over extended time scales under adverse wellbore

464 conditions.

465

474

**References**

476

477 1.        Tong, D.;  Zhang, Q.;  Zheng, Y.;  Caldeira, K.;  Shearer, C.;  Hong, C.;  Qin, Y.; Davis, S. J.,
478 Committed emissions from existing energy infrastructure jeopardize 1.5 °C climate target. *Nature* **2019,**
479 *572* (7769), 373-377.
480 2.        Agency, I. E., The Role of CO2 Storage. IEA: Paris, 2019; Vol. Exploring Clean Energy Pathways.
481 3.        Jafariesfad, N.;  Sangesland, S.;  Gawel, K.; Torsæter, M., New Materials and Technologies for
482 Life-Lasting Cement Sheath: A Review of Recent Advances. *SPE Drilling & Completion* **2020,** *35* (02), 262-
483 278.
484 4.        Todorovic, J.;  Raphaug, M.;  Lindeberg, E.;  Vralstad, T.; Buddensiek, M. L., Remediation of
485 Leakage through Annular Cement Using a Polymer Resin: a Laboratory Study. *8th Trondheim Conference*
486 *on Co2 Capture, Transport and Storage* **2016,** *86*, 442-449.
487 5.        Genedy, M.;  Kandil, U. F.;  Matteo, E. N.;  Stormont, J.; Taha, M. M. R., A new polymer
488 nanocomposite repair material for restoring wellboreseal integrity. *International Journal of Greenhouse*
489 *Gas Control* **2017,** *58*, 290-298.
490 6.        Genedy, M.;  Matteo, E. N.;  Stenko, M.;  Stormont, J. C.; Taha, M. R., Nanomodified Methyl
491 Methacrylate Polymer for Sealing of Microscale Defects in Wellbore Systems. *J. Mater. Civ. Eng.* **2019,** *31*
492 (7).

20

493    7.     Kirkland, C. M.; Hiebert, R.; Hyatt, R.; McCloskey, J.; Kirksey, J.; Thane, A.; Cunningham, A. B.;
494  Gerlach, R.; Spangler, L.; Phillips, A. J., Direct Injection of Biomineralizing Agents to Restore Injectivity
495  and Wellbore Integrity. *SPE Production & Operations* **2020,** *Preprint* (Preprint), 8.

496    8.     Kirkland, C. M.; Thane, A.; Hiebert, R.; Hyatt, R.; Kirksey, J.; Cunningham, A. B.; Gerlach, R.;
497  Spangler, L.; Phillips, A. J., Addressing wellbore integrity and thief zone permeability using microbially-
498  induced calcium carbonate precipitation (MICP): A field demonstration. *Journal of Petroleum Science*
499  *and Engineering* **2020,** *190*, 107060.

500    9.     Phillips, A. J.; Troyer, E.; Hiebert, R.; Kirkland, C. M.; Gerlach, R.; Cunningham, A.; Spangler, L.;
501  Kirksey, J.; Rowe, W.; Esposito, R., Enhancing wellbore cement integrity with microbially induced calcite
502  precipitation (MICP): a field scale demonstration. *Journal of Petroleum Science and Engineering* **2018,**
503  *171*, 1141-1148.

504    10.    Fujita, Y.; Ferris, E. G.; Lawson, R. D.; Colwell, F. S.; Smith, R. W., Calcium carbonate
505  precipitation by ureolytic subsurface bacteria. *Geomicrobiol. J.* **2000,** *17* (4), 305-318.

506    11.    Krajewska, B., Ureases I. Functional, catalytic and kinetic properties: A review. *Journal of*
507  *Molecular Catalysis B-Enzymatic* **2009,** *59* (1-3), 9-21.

508    12.    Oppenheimer-Shaanan, Y.; Sibony-Nevo, O.; Bloom-Ackermann, Z.; Suissa, R.; Steinberg, N.;
509  Kartvelishvily, E.; Brumfeld, V.; Kolodkin-Gal, I., Spatio-temporal assembly of functional mineral
510  scaffolds within microbial biofilms. *Npj Biofilms and Microbiomes* **2016,** *2*.

511    13.    Stocks-Fischer, S.; Galinat, J. K.; Bang, S. S., Microbiological precipitation of CaCO3. *Soil Biol.*
512  *Biochem.* **1999,** *31* (11), 1563-1571.

513    14.    Zambare, N. M.; Naser, N. Y.; Gerlach, R.; Chang, C. B., Mineralogy of microbially induced
514  calcium carbonate precipitates formed using single cell drop-based microfluidics. *Scientific Reports* **2020,**
515  *10* (1), 17535.

516    15.    Kirkland, C. M.; Norton, D.; Thane, A.; Hiebert, R.; Hommel, J.; Kirksey, J.; Esposito, R.;
517  Cunningham, A.; Gerlach, R.; Spangler, L.; Phillips, A. In *Biomineralization and wellbore integrity: a*
518  *microscopic solution to subsurface fluid migration*, 14th Greenhouse Gas Control Technologies
519  Conference, Melbourne, Australia, 21-26 October 2018; Melbourne, Australia, 2019.

520    16.    Phillips, A. J.; Cunningham, A. B.; Gerlach, R.; Hiebert, R.; Hwang, C.; Lomans, B. P.; Westrich,
521  J.; Mantilla, C.; Kirksey, J.; Esposito, R.; Spangler, L., Fracture Sealing with Microbially-Induced Calcium
522  Carbonate Precipitation: A Field Study. *Environ. Sci. Technol.* **2016,** *50* (7), 4111-4117.

523    17.    Cuthbert, M. O.; McMillan, L. A.; Handley-Sidhu, S.; Riley, M. S.; Tobler, D. J.; Phoenix, V. R., A
524  Field and Modeling Study of Fractured Rock Permeability Reduction Using Microbially Induced Calcite
525  Precipitation. *Environ. Sci. Technol.* **2013,** *47* (23), 13637-13643.

526    18.    Minto, J. M.; MacLachlan, E.; El Mountassir, G.; Lunn, R. J., Rock fracture grouting with
527  microbially induced carbonate precipitation. *Water Resour. Res.* **2016,** *52* (11), 8810-8827.

528    19.    Tobler, D. J.; Minto, J. M.; El Mountassir, G.; Lunn, R. J.; Phoenix, V. R., Microscale Analysis of
529  Fractured Rock Sealed With Microbially Induced CaCO3 Precipitation: Influence on Hydraulic and
530  Mechanical Performance. *Water Resour. Res.* **2018,** *54* (10), 8295-8308.

531    20.    Kirkland, C. M.; Norton, D.; Firth, O.; Eldring, J.; Cunningham, A. B.; Gerlach, R.; Phillips, A. J.,
532  Visualizing MICP with X-ray uCT to enhance cement defect sealing. *International Journal of Greenhouse*
533  *Gas Control* **2019,** *86*, 93 - 100

534    21.    Feder, M. J.; Akyel, A.; Morasko, V. J.; Gerlach, R.; Phillips, A. J., Temperature-dependent
535  inactivation and catalysis rates of plant-based ureases for engineered biomineralization. *Engineering*
536  *Reports* **2020,** *n/a* (n/a), e12299.

537    22.    Herigstad, B.; Hamilton, M.; Heersink, J., How to optimize the drop plate method for
538  enumerating bacteria. *J. Microbiol. Methods* **2001,** *44* (2), 121-129.

539    23.    Jung, D.; Biggs, H.; Erikson, J.; Ledyard, P. U., New colorimetric reaction for endpoint,
540  continuous-flow and kinetic measurement of urea *Clin. Chem.* **1975,** *21* (8), 1136-1140.

21

541    24.    Shashank, B. S.; Minto, J. M.; Singh, D. N.; El Mountassir, G.; Knapp, C. W., Guidance for
542    Investigating Calcite Precipitation by Urea Hydrolysis for Geomaterials. *J. Test. Eval.* **2018,** *46* (4), 1527-
543    1538.
544    25.    Mitchell, A. C.; Phillips, A.; Schultz, L.; Parks, S.; Spangler, L.; Cunningham, A. B.; Gerlach, R.,
545    Microbial CaCO3 mineral formation and stability in an experimentally simulated high pressure saline
546    aquifer with supercritical CO2. *International Journal of Greenhouse Gas Control* **2013,** *15*, 86-96.
547    26.    Verba, C.; Thurber, A. R.; Alleau, Y.; Koley, D.; Colwell, F.; Torres, M. E., Mineral changes in
548    cement-sandstone matrices induced by biocementation. *International Journal of Greenhouse Gas
549    Control* **2016,** *49*, 312-322.
550    27.    Phillips, A. J.; Eldring, J.; Hiebert, R.; Lauchnor, E.; Mitchell, A. C.; Cunningham, A.; Spangler,
551    L.; Gerlach, R., Design of a meso-scale high pressure vessel for the laboratory examination of
552    biogeochemical subsurface processes. *Journal of Petroleum Science and Engineering* **2015,** *126*, 55-62.
553    28.    Phillips, A. J.; Lauchnor, E.; Eldring, J.; Esposito, R.; Mitchell, A. C.; Gerlach, R.; Cunningham,
554    A. B.; Spangler, L. H., Potential CO2 Leakage Reduction through Biofilm-Induced Calcium Carbonate
555    Precipitation. *Environ. Sci. Technol.* **2013,** *47* (1), 142-149.
556    29.    Kirkland, C. M.; Zanetti, S.; Grunewald, E.; Walsh, D. O.; Codd, S. L.; Phillips, A. J., Detecting
557    Microbially Induced Calcite Precipitation in a Model Well-Bore Using Downhole Low-Field NMR. *Environ.
558    Sci. Technol.* **2017,** *51* (3), 1537-1543.
559    30.    Ferris, F. G.; Stehmeier, L. G.; Kantzas, A.; Mourits, F. M., Bacteriogenic mineral plugging. *J. Can.
560    Pet. Technol.* **1996,** *35* (8), 56-61.
561    31.    Illeova, V.; Polakovic, M.; Stefuca, V.; Acai, P.; Juma, M., Experimental modelling of thermal
562    inactivation of urease. *J. Biotechnol.* **2003,** *105* (3), 235-243.
563    32.    Beckers, G.; Bendt, A. K.; Krämer, R.; Burkovski, A., Molecular identification of the urea uptake
564    system and transcriptional analysis of urea transporter- and urease-encoding genes in Corynebacterium
565    glutamicum. *J. Bacteriol.* **2004,** *186* (22), 7645-7652.
566    33.    Mobley, H. L.; Island, M. D.; Hausinger, R. P., Molecular biology of microbial ureases.
567    *Microbiological Reviews* **1995,** *59* (3), 451-480.
568    34.    Ma, L.; Pang, A.-P.; Luo, Y.; Lu, X.; Lin, F., Beneficial factors for biomineralization by ureolytic
569    bacterium Sporosarcina pasteurii. *Microbial Cell Factories* **2020,** *19* (1), 12.
570    35.    Secchi, E.; Vitale, A.; Mino, G. L.; Kantsler, V.; Eberl, L.; Rusconi, R.; Stocker, R., The effect of
571    flow on swimming bacteria controls the initial colonization of curved surfaces. *Nature Communications*
572    **2020,** *11* (1).
573    36.    Hommel, J.; Akyel, A.; Frieling, Z.; Phillips, A. J.; Gerlach, R.; Cunningham, A. B.; Class, H., A
574    Numerical Model for Enzymatically Induced Calcium Carbonate Precipitation. *Applied Sciences* **2020,** *10*
575    (13).
576    37.    Cunningham, A. B.; Class, H.; Ebigbo, A.; Gerlach, R.; Phillips, A. J.; Hommel, J., Field-scale
577    modeling of microbially induced calcite precipitation. *Computational Geosciences* **2019,** *23* (2), 399-414.
578    38.    Landa Marbán, D.; Tveit, S.; Kumar, K.; Gasda, S., *Practical approaches to study microbially
579    induced calcite precipitation at the field scale*. 2020.
580

22