

## RESEARCH ARTICLE


# Multicellular magnetotactic bacteria are genetically heterogeneous consortia with metabolically differentiated cells

George A. Schaible<sup>1,2</sup>, Zackary J. Jay<sup>1,2,3</sup>, John Cliff<sup>4a</sup>, Frederik Schulz<sup>5</sup>, Colin Gauvin<sup>2,3</sup>, Danielle Goudeau<sup>5</sup>, Rex R. Malmstrom<sup>5</sup>, S. Emil Ruff<sup>6</sup>, Virginia Edgcomb<sup>7</sup>, Roland Hatzenpichler<sup>1,2,3,8\*</sup>

**1** Department of Chemistry and Biochemistry, Montana State University, Bozeman, Montana, United States of America, **2** Center for Biofilm Engineering, Montana State University, Bozeman, Montana, United States of America, **3** Thermal Biology Institute, Montana State University, Bozeman, Montana, United States of America, **4** Environmental Molecular Sciences Laboratory, Pacific Northwest National Laboratory, Richland, Washington, United States of America, **5** Department of Energy Joint Genome Institute, Berkeley, California, United States of America, **6** Ecosystems Center and Bay Paul Center, Marine Biological Laboratory, Woods Hole, Massachusetts, United States of America, **7** Woods Hole Oceanographic Institution, Falmouth, Massachusetts, United States of America, **8** Department of Microbiology and Cell Biology, Montana State University, Bozeman, Montana, United States of America

<sup>a</sup> Current address: National Security Directorate, Oak Ridge National Laboratory, Oak Ridge, Tennessee, United States of America

\* [roland.hatzenpichler@montana.edu](mailto:roland.hatzenpichler@montana.edu)



## OPEN ACCESS

**Citation:** Schaible GA, Jay ZJ, Cliff J, Schulz F, Gauvin C, Goudeau D, et al. (2024) Multicellular magnetotactic bacteria are genetically heterogeneous consortia with metabolically differentiated cells. *PLoS Biol* 22(7): e3002638. <https://doi.org/10.1371/journal.pbio.3002638>

**Academic Editor:** Wenyng Shou, Fred Hutchinson Cancer Research Center, UNITED STATES

**Received:** December 18, 2023

**Accepted:** April 24, 2024

**Published:** July 11, 2024

**Copyright:** This is an open access article, free of all copyright, and may be freely reproduced, distributed, transmitted, modified, built upon, or otherwise used by anyone for any lawful purpose. The work is made available under the [Creative Commons CC0](https://creativecommons.org/licenses/by/4.0/) public domain dedication.

**Data Availability Statement:** The single consortia metagenomes of MMB generated in this study are available on JGI's IMG/M under the genome numbers 3300028595, 3300034483-3300034486, and 3300034488-3300034505. The genome sequences of *Ca. M. multicellularis* and *Ca. M. HK-1* are available at NCBI Genbank under accession numbers GCA\_000516475 and JPDT000000000, respectively. Magnetosome sequences for *Ca. Desulfamplus magnetomortis* BW-1, *Ca. Magnetananas rongchenensis* RPA, and *MMP XL-1* are available at GenBank under accession

## Abstract

Consortia of multicellular magnetotactic bacteria (MMB) are currently the only known example of bacteria without a unicellular stage in their life cycle. Because of their recalcitrance to cultivation, most previous studies of MMB have been limited to microscopic observations. To study the biology of these unique organisms in more detail, we use multiple culture-independent approaches to analyze the genomics and physiology of MMB consortia at single-cell resolution. We separately sequenced the metagenomes of 22 individual MMB consortia, representing 8 new species, and quantified the genetic diversity within each MMB consortium. This revealed that, counter to conventional views, cells within MMB consortia are not clonal. Single consortia metagenomes were then used to reconstruct the species-specific metabolic potential and infer the physiological capabilities of MMB. To validate genomic predictions, we performed stable isotope probing (SIP) experiments and interrogated MMB consortia using fluorescence in situ hybridization (FISH) combined with nanoscale secondary ion mass spectrometry (NanoSIMS). By coupling FISH with bioorthogonal noncanonical amino acid tagging (BONCAT), we explored their in situ activity as well as variation of protein synthesis within cells. We demonstrate that MMB consortia are mixotrophic sulfate reducers and that they exhibit metabolic differentiation between individual cells, suggesting that MMB consortia are more complex than previously thought. These findings expand our understanding of MMB diversity, ecology, genomics, and physiology, as well as offer insights into the mechanisms underpinning the multicellular nature of their unique lifestyle.

numbers HF547348, KY084568, and ON204283; ON204284, respectively. Python and R code used to analyze BONCAT data are available on the Zenodo open repository (<https://doi.org/10.5281/zenodo.11060878>).

**Funding:** This study was funded through NASA Exobiology program award NNX17AK85G to R.H. and NASA FINESST award 80NSSC20K1365 to G. S. and R.H. A portion of this research was performed under the Community Sciences Program (awards DOI: [10.46936/10.25585/60001107](https://doi.org/10.46936/10.25585/60001107) and DOI: [10.46936/10.25585/60001212](https://doi.org/10.46936/10.25585/60001212)) and used resources at the DOE Joint Genome Institute (<https://ror.org/04xm1d337>), which is a DOE Office of Science User Facility operated under Contract No. DE-AC02-05CH11231. A portion of this research was performed under the Facilities Integrating Collaborations for User Science (FICUS) program under awards DOI: [10.46936/fics.proj.2017.49972/6000002](https://doi.org/10.46936/fics.proj.2017.49972/6000002) to R.H. and [10.46936/fics.proj.2020.51544/60000211](https://doi.org/10.46936/fics.proj.2020.51544/60000211) to R.H. and used resources at the Environmental Molecular Sciences Laboratory (<https://ror.org/04rc0xn13>), which is a DOE Office of Science User Facilities operated under Contract No. DE-AC05-76RL01830. Fluorescence and Raman microscopy imaging was made possible by The Center for Biofilm Engineering Imaging Facility at Montana State University, which is supported by funding from the NSF MRI Program (2018562), the M. J. Murdock Charitable Trust (202016116), the US Department of Defense (77369LSRIP), and by the Montana Nanotechnology Facility (an NNCI member supported by NSF Grant ECCS-2025391). Montana State University's Confocal Raman microscope was acquired with support by the National Science Foundation (DBI-1726561) and the M. J. Murdock Charitable Trust (SR-2017331). The National Institute of General Medical Sciences (P30GM140963) provided support to C.G. The Simons Foundation (824763) provided support to S.E.R. The funders had no role in the study design, data collection and analysis, decision to publish, or preparation of the manuscript.

**Competing interests:** The authors have declared that no competing interests exist.

**Abbreviations:** ANI, average nucleotide identity; BONCAT, bioorthogonal noncanonical amino acid tagging; FISH, fluorescence in situ hybridization; HSI, hue saturated image; LSSM, Little Sippewissett Salt Marsh; MAG, metagenome assembled genome; MGC, magnetosome gene cluster; MMB, multicellular magnetotactic bacteria; NanoSIMS, nano-scale secondary ion mass spectrometry; RFI, relative fluorescence intensity; SCM, Single Consortium Metagenome; SEM,

## Introduction

Multicellular lifeforms are defined as organisms that are built from several or many cells of the same species [1,2]. Beyond this, other characteristics of multicellularity include a specific shape and organization, a lack of individual cell autonomy or competition between cells, and a display of cell-to-cell signaling and coordinated response to external stimuli [3]. The transition from a single cell to a cooperative multicellular organism is an important evolutionary event that has independently occurred at least 50 times across the tree of life [4]. This suggests that the development of multicellularity can occur in any species given proper selective pressure [5,6]. Prior research on the transition of unicellular to multicellular organisms has largely focused on eukaryotic model systems such as choanoflagellates [7], fungi [8], and algae [9]. Multicellularity within the domain bacteria is uncommon as compared to eukaryotes [10], yet this lifestyle likely first evolved approximately >3 billion years ago [11]. Examples of multicellularity within the domain bacteria include filamentous cyanobacteria (e.g., *Anabaena cylindrica*), mycelia-forming actinomyces (e.g., *Streptomyces coelicolor*), swarming myxobacteria (e.g., *Myxococcus xanthus*), centimeter-long cable bacteria (e.g., *Electrothrix* sp.), and the recently discovered liquid-crystal colonies of Neisseriaceae (e.g., *Jeongeupia sacculi* sp. nov. HS-3) [6,12,13]. While capable of multicellular growth, each of these microbes undergoes a unicellular stage at some point in their life cycle.

Currently, the only known example of purportedly obligate multicellularity—an organism without a detectable unicellular stage—within the domain bacteria are several species of multicellular magnetotactic bacteria (MMB; we use the terms “MMB consortia” and “MMB” interchangeably) [14,15]. Historically, MMB have been described as “aggregates” of cells [16], which could imply that individual cells assemble to form a multicellular aggregate, akin to the early stages of biofilm formation [6,16]. In this study, we use the terms “consortium” (singular) and “consortia” (plural) to describe the unique form of multicellularity observed for MMB.

MMB are symmetrical single-species consortia composed of 15 to 86 cells [17] of Desulfobacterota (formerly Deltaproteobacteria) arranged in a single layer enveloping an acellular, central compartment (Fig 1A and 1B). Consortia range in size from 3 to 12  $\mu\text{m}$  in diameter [18–20]. Within the Desulfobacterota, MMB form an uncultured, monophyletic family that is distinct from several physiologically and genetically well-characterized unicellular relatives, suggesting a common ancestor that achieved a multicellular state [21–23].

MMB are unique among bacteria because their life cycle lacks a unicellular stage. Instead, MMB replicate by the entire consortium doubling its cell number and volume before separating into 2 seemingly identical consortia, as has been observed via brightfield, epifluorescence, and scanning electron microscopy (SEM) [15,18,24–26]. Studies using fluorescence in situ hybridization (FISH) have identified MMB exclusively in a multicellular state [14,25,27]. Live-dead staining experiments revealed that when cells become separated from the consortium, for example because of osmotic or mechanical stress, the consortium dismantles. This is followed by an immediate loss of magnetic orientation and motility and eventual loss of membrane integrity, leading to the death of both the separated cells and the consortium [26]. MMB consortia consistently exhibit a high degree of magnetic optimization, excluding the possibility that the consortium is a mere aggregation of cells without underlying self-organization [28,29]. Each cell within the consortium has multiple flagella, resulting in the whole consortium being peritrichously flagellated [19,30]. When environmental conditions change, such as alterations in light exposure or magnetic fields, a coordinated response in motility occurs within fractions of a second [30,31]. This collective response implies inter-cellular communication among individual cells, which is hypothesized to occur through the central acellular volume that the cells surround [18]. Previous work has hypothesized that the absence of a single


scanning electron microscopy; SIP, stable isotope probing; SNP, single-nucleotide polymorphism; TA, toxin-antitoxin.

cell stage in MMB might be necessary to maintain the acellular volume at the center of each MMB or that their larger size is needed to evade predation by protists [15]. Currently, there is no evidence to support or refute these hypotheses.

In addition to their unique obligate multicellular life cycle, MMB have an organelle called the magnetosome [32]. The magnetosome is a lipid vesicle that encapsulates biomineralized magnetite ( $\text{Fe}_3\text{O}_4$ ) and/or greigite ( $\text{Fe}_3\text{S}_4$ , Fig 1C). Dozens of these organelles are organized in chains that allow MMB to sense and orient themselves along Earth's geomagnetic field in a phenomenon termed magnetotaxis. Magnetosome formation is controlled by a magnetosome gene cluster (MGC, S1 Appendix Text) that encodes several proteins involved in the formation, alignment, and maturation of the organelles [33,34]. The presence of magnetosomes in MMB can be exploited to physically enrich them from environmental samples using a magnet (S1 and S2 Videos). This is particularly important considering that MMB have not yet been successfully cultured and are of low relative abundance (0.001–2%) in their habitats, sulfidic brackish and marine sediments [35–37]. Interestingly, non-magnetotactic multicellular bacteria that affiliate to the same family as MMB (Desulfobacterales) and share many morphological similarities with them have been found in freshwater sediments [38]; these bacteria could be interpreted as MMB that at the time of sampling did not express their magnetosomes or had lost their magnetotactic ability.

While past studies have presented fascinating insights into the cellular organization of MMB and their diverse abilities to sense the environment via light and electron microscopy [22,31,39], their recalcitrance to cultivation has hindered progress towards a better understanding of their physiology and genomics. With the exception of a study that demonstrated chemotactic response of MMB consortia to small molecular weight organic acids [39], questions about their physiology remain unaddressed, and hypotheses about the potential for metabolic differentiation or a division of labor between individual cells within a consortium have not been experimentally tested.

To address these knowledge gaps, we investigated the taxonomic diversity, genomics, physiology, metabolic differentiation, and clonality of MMB inhabiting a tidal pool. To investigate



**Fig 1. Morphology and structure of MMB.** (A) Cartoon depicting the morphology and internal organization of an MMB consortium. At the center of each MMB consortium lies an acellular space that is surrounded by a single layer of cells. Each cell harbors magnetosome organelles (black polygons aligned along cytoskeleton-like filaments), compartments for carbon or energy storage (gray circles), as well as other, currently unidentified structures. Scale bar ca. 1  $\mu\text{m}$ . (B) SEM image of 2 MMB magnetically enriched from LSSM, possibly undergoing division. Scale bar, 1  $\mu\text{m}$ . (C) Backscatter electron microscopy image of magnetosome chains within MMB cells (arrow). Magnetosome minerals appear to have 4–8 visible facets and are approximately 30–60 nm in diameter. Scale bar, 300 nm. Contrast and brightness of image (C) was increased for better visualization. LSSM, Little Sippewissett Salt Marsh; MMB, multicellular magnetotactic bacteria; SEM, scanning electron microscopy.

<https://doi.org/10.1371/journal.pbio.3002638.g001>

the diversity of MMB within this environment, we sequenced the Single Consortium Metagenomes (SCMs) of 22 individual MMB consortia, representing 8 distinct species of MMB. Comparing the SCMs, we were able to quantify the extent of single-nucleotide polymorphisms (SNPs) between cells composing individual MMB consortia. Our analyses showed that MMB exhibit genetic diversity within a single consortium, indicating that they are not composed of clonal cells. Physiological predictions were established through the reconstruction of species-specific metabolic models. We tested these predictions by performing stable isotope probing (SIP) experiments and analyzing individual consortia using FISH, nanoscale secondary ion mass spectrometry (NanoSIMS), and bioorthogonal noncanonical amino acid tagging (BONCAT). Our results demonstrate that MMB are mixotrophic sulfate reducers and that individual cells within MMB consortia exhibit dramatically different rates of substrate uptake, indicating metabolic differentiation, as well as localized protein synthesis activity.


## Results and discussion

### Genomic features and phylogenetic analysis of MMB

MMB were recovered from sulfidic sediments collected from a tidal pool in Little Sippewissett Salt Marsh (LSSM; Falmouth, Massachusetts, United States of America; [S1A and S1B Fig](#)). This sample site was selected based on the ability to magnetically enrich ([S1 and S2 Videos](#)) relatively large quantities of MMB, as previously demonstrated [[27,31](#)]. MMB were stained with SYBR green and individual consortia were sorted from a magnetically enriched pellet using fluorescence-activated cell sorting and the DNA of individual sorted MMB was amplified by multiple displacement amplification before Illumina sequencing. From this sample, the SCMs of 22 individual MMB were recovered ([Fig 2](#) and Table A in [S2 Appendix](#)). The GC content of the SCMs ranged from 36.2% to 38.4%, which is similar to the GC content observed in previously published MMB draft genomes [[22,40,41](#)]. The average and median size of the 22 new SCMs was 7.7 Mb, with a range from 6.1 to 9.1 Mb (Table A in [S2 Appendix](#)). Prior to this study, only 3 draft genomes of MMB had been sequenced. These genomes exhibited significant variations in size, ranging from 14.3 Mb for *Ca. Magnetomorum* sp. HK-1 [[40](#)], 12.5 Mb for *Ca. Magnetoglobus multicellularis* [[22](#)], and 8.5 Mb for MMP XL-1 [[41](#)], although the MMP XL-1 genome is not publicly available. The genome sizes of *Ca. M. multicellularis* and *Ca. M. sp. HK-1* could be conflated due to contamination or the combination of sequence data into the same final bin, as discussed in the respective studies [[22,40](#)] and evidenced by our own evaluations of genome contamination ([Fig 2A](#)).

Only 14 of the 22 SCMs contained 16S rRNA genes (Table A in [S2 Appendix](#)). These sequences, together with publicly available 16S rRNA sequences of MMB as well as those of their single-cell relatives *Desulfosarcina variabilis* and *Ca. Desulfamplus magnetomortis* BW-1, were used to construct a phylogenetic tree (Table B in [S2 Appendix](#)). This analysis revealed the presence of 5 phylogenetically distinct genera of MMB in LSSM with high bootstrap support (>75%) ([S2 Fig](#)). Analysis of amplicon sequence data obtained in this study and sequences from a previous study at LSSM [[27](#)] showed that Group 1 MMB was most abundant in the sample site, constituting 61% of all 16S rRNA genes. Groups 2, 4, 5, and 3 accounted for 21%, 6.5%, 6.5%, and 5% of the 16S rRNA genes, respectively ([S2 and S3 Figs](#)).

Phylogenomic analysis of 6 bacterial single copy genes found in all recovered MMB SCMs yielded a topology consistent with the phylogeny derived from the 16S rRNA gene sequences ([Figs 2](#) and [S2](#) and Table C in [S2 Appendix](#)). Similarly, whole genome and 16S rRNA-specific average nucleotide identity (ANI) comparison resolved 8 unique species of MMB with >96% ANI. We assigned type genomes for each new MMB species and named them after scientists



**Fig 2. Genomic and phylogenetic analysis of all publicly available MMB MAGs and the 22 SCMs generated in this study.** (A) Maximum-likelihood tree, inferred with FastTree, using a concatenated set of 6 conserved COGs present in all entries. Ultrafast bootstrap support values and selected genome statistics are listed. The color codes for the SCM full-length 16S rRNA gene identity and (B) average genome nucleotide identity heat maps of the 8 newly identified MMB species compared to 2 available MMB reference genomes (*Ca. M. multicellularis* and *Ca. Magnetomorum sp. HK-1*). For a phylogenetic tree of all publicly available MMB 16S rRNA gene sequences, see S2 Fig. For an exhaustive sequence identity analyses of 16S rRNA and whole genomes of MMB, see S3–S5 Figs. The data underlying this figure can be found in Tables A and C in S2 Appendix. MAG, metagenome assembled genome; MMB, multicellular magnetotactic bacteria; SCM, Single Consortium Metagenome.

<https://doi.org/10.1371/journal.pbio.3002638.g002>

who have greatly advanced our knowledge of MMB (S1 Appendix and Table D in S2 Appendix).

### Clonality within MMB

MMB have historically been assumed to be clonal due to the synchronized replication of cells during division, which should result in genetically identical daughter cells in the same consortium [15,24]. Additionally, obligate multicellularity has traditionally been thought to perpetuate a clonal population [42]. Although MMB maintain an obligate multicellular life cycle, the degree to which clonality exists within a single consortium has never been experimentally tested. Currently, the only evidence suggesting that cells within MMB are closely related


comes from analyses of the 16S rRNA genes from cells of a single genome amplified MMB consortium [40] and a FISH studies demonstrating that cells within individual MMB have identical 16S rRNA sequences [25,27,43,44].

We set out to test the hypothesis of clonality using comparative genomics of the 22 MMB SCMs recovered in this study. Reads from each individual SCM were mapped to the corresponding genome bins to quantify SNPs within a single MMB consortium. As a procedural control, 10, 30, 60, and 100 cells of a clonal culture of *Pseudomonas putida* were sorted to construct a mock multicellular consortium. The DNA of MMB consortia and *P. putida* controls were amplified using multiple displacement amplification and sequenced using Illumina short read sequencing. Our analysis of the SCMs revealed for the first time that MMB consortia are genomically heterogeneous and thus do not fit the model of clonality for obligate multicellular organisms (Fig 3A). MMB from LSSM contain up to 2 orders of magnitude more SNP differences within a single consortium as compared to the same number of cells from the clonal control ( $p < 7.3 \times 10^{-9}$ ), with an estimated range of 157 to 789 SNPs in individual SCMs (Fig 3 and Table E in S2 Appendix). Other environmental microbes co-sorted with MMB showed an SNP rate similar to the clonal control and an SNP rate statistically different from the MMB ( $p < 2.4 \times 10^{-6}$ ), illustrating the uniqueness of MMB. Wielgoss and colleagues performed a similar analysis on fruiting bodies of the aggregative multicellular bacterium *Myxococcus xanthus* in which a comparison of the genomes of cells in fruiting bodies revealed 30 SNP differences between lineages originated from a recent single ancestral genotype [45]. Furthermore, nearly half the mutations detected in the *M. xanthus* genomes occurred in the same 6 genes, suggesting there was a strong selection for socially relevant genes, such as a histidine kinase (signal transduction) and methyltransferase (gene expression). Positive selection upon cooperative genes may promote diversity within the organism as a mechanism to increase fitness within spatiotemporally variable environments and protect against social cheaters [46].

To investigate if the genetic heterogeneity within MMB contributes to an increased fitness of the organism, we identified the genes containing SNPs and calculated the corresponding ratio of non-synonymous (dN) to synonymous (dS) substitutions. This analysis showed that the SNP differences within the SCMs of MMB appear to be random with no single gene or category of genes exclusively impacted by the SNPs within or across MMB consortia and that most genes were subject to negative (purifying) selection (Fig 3B and Table F in S2 Appendix). SNPs with a high dN/dS ratio were predominantly found in unannotated genes, such as hypothetical proteins, and were found to be subject to positive selection (S6 Fig). Such genes could ultimately drive functional divergence within the consortium. Other benefits of genomic heterogeneity within MMB are not readily apparent and could be attributed to errors during DNA replication or damaging effects of mutagens. However, it has been shown that a single mutation can lead to a division of labor in bacteria [47]. At this point, it is unclear whether any of the changes we observe in the genomes contained within individual MMB would lead to phenotypic differentiation between the adjacent cells.

## Genome annotation


Metabolic reconstructions of the MMB SCMs (Fig 4 and Table G in S2 Appendix) revealed that all MMB are capable of heterotrophic sulfate reduction and can use acetate, succinate, and propionate as carbon donors and/or electron sources, consistent with previous genomic analyses [22,40]. The SCMs show that LSSM MMB have highly similar metabolic potential. One exception is *Ca. M. sippewissettense*, which lacks the ability to utilize acetyl-coenzyme A (CoA) synthetase and is unable to use acetate, instead likely relying on lactate dehydrogenase to metabolize lactate, a substrate the other species are not capable of using. None of the SCMs



**Fig 3. Clonality analysis of individual MMB consortia.** (A) Individual reads were mapped to the same genome bin for each of the 22 SCMs. This analysis revealed that the genomes of cells within MMB consortia have a higher SNP rate (SNP expressed as variations per Mb) as compared to a clonal *Pseudomonas* sp. control ( $p < 7.3 \times 10^{-9}$ ,  $n = 10, 30, 60,$  and  $100$  *Pseudomonas* cells) and other environmental cells ( $p < 2.4 \times 10^{-6}$ , e.g., “Other”). (B) The 3 sample categories showed no statistically significant difference in terms of their overall ratio of non-synonymous to synonymous substitutions (dN/dS). Most values were between 0 and 0.5, indicating that there is predominantly strong negative (purifying) selection and that SNPs typically do not lead to changes in the amino acid sequence. S6 Fig provides additional details on genes affected by positive and negative selection. The color of each SCM corresponds to the color identifying each unique species in Fig 2. Statistical analyses were performed using a pairwise *t* test with the Bonferroni *p*-adjusted method. The data underlying this figure can be found in Tables E and F in S2 Appendix. MMB, multicellular magnetotactic bacteria; SCM, Single Consortium Metagenome; SNP, single-nucleotide polymorphism.

<https://doi.org/10.1371/journal.pbio.3002638.g003>

contain acetaldehyde dehydrogenase, indicating that MMB are not capable of alcohol fermentation. We resolved a complete glycolysis pathway and TCA cycle as well as reductive CoA pathway in all SCMs. The presence of these genes suggests that MMB in LSSM are capable of both heterotrophic and autotrophic growth using sulfate reduction coupled to hydrogen metabolism, by means of *hyaA/B* and *hybA/B* complexes and oxidative phosphorylation. MMB are genetically capable of shuttling electrons using complexes I, II, and V of the oxidative phosphorylation pathway using F-type ATP synthase complexes, although partial V/A



**Fig 4. Metabolic potential of the 8 MMB species in LSSM.** Arrows without circles indicate presence of the respective enzyme or pathway in all bins. Circles indicate complete presence (black), partial presence (gray), or missing (white) genes in each species. A full list of genes used to construct this figure can be found in Table G in S2 Appendix. LSSM, Little Sippewissett Salt Marsh; MMB, multicellular magnetotactic bacteria.

<https://doi.org/10.1371/journal.pbio.3002638.g004>

type ATP synthase were found in *Ca. Magnetoglobus martinsiae* and *Ca. Magnetomorum sippewissettense*. In addition, they encode a full Nqr (Na<sup>+</sup>-transporting NADH:ubiquinone oxidoreductase) complex that can move electrons from NADH to ubiquinone with the translocation of a Na<sup>+</sup> across the membrane. Cytochrome bd oxidase subunits I and II are present in all SCMs, except *Ca. Magnetoglobus farinai*, and could be used to respire molecular oxygen (O<sub>2</sub>) using electrons from cytochrome c or quinols [48]. All species of MMB from LSSM encode rubrerythrin and superoxide reductase, suggesting the possibility that O<sub>2</sub> could instead be detoxified by the cytochrome bd oxidase (Table G in S2 Appendix) [22,49]. Electrons can also be removed by the reduction of protons to molecular hydrogen (H<sub>2</sub>) by group 1 nickel-iron hydrogenases. The H<sub>2</sub> can then diffuse across the membrane where HybA/B could oxidize the H<sub>2</sub>, yielding 2 electrons and 2 protons. From there, cytochrome c can shuttle the electrons to the Dsr and Qmo complexes for dissimilatory sulfate reduction.

The MMB SCMs encode several divalent metal transporters, including FoaAB ferrous iron and FepBDC ferric iron transport proteins, indicating they are capable of using both Fe(II) and Fe(III). All SCMs encode phosphate transporters as well as oligopeptide and branched-chain amino acid transporters. Genes for polyamine transport were recovered in the SCMs and may provide resistance to environmental stress such as osmotic pressure and reactive oxygen species [50]. Additionally, each SCM encodes a glycine betaine transporter but does not encode a betaine reductase, indicating that MMB do not use glycine betaine as a nitrogen source but as an osmoprotectant [51]. All MMB species in LSSM, except *Ca. M. sippewissettense*, encode an Amt transporter to transport ammonia into cells that can then be converted into glutamine or glutamate and fed into anabolic pathways. Additionally, each species



encodes the NitT/TauT system for nitrate, sulfonate, and bicarbonate transport into cells. The SCMs showed that MMB are capable of synthesizing all canonical amino acids except cysteine and lack cysteine prototrophy genes. Cultures of single-celled magnetotactic bacteria have been found to require the addition of cysteine for growth, suggesting that many magnetotactic bacteria, including MMB, cannot synthesize their own cysteine [52]. The inability to synthesize a sulfurous amino acid is surprising given that most magnetotactic bacteria, including all known MMB, live in sulfur-rich environments.

Previous studies using transmission electron microscopy and Nile Red staining have found large vesicles within MMB cells that have been attributed to carbon/energy or phosphate storage [19,53,54]. Metabolic analysis of the SCMs showed that acetyl-CoA could be condensed and polymerized to polyhydroxybutyrate (PHB) for storage. Furthermore, all necessary genes were identified for  $\beta$ -oxidation using triacylglycerol synthesized from the acylation of glycerol-3P with acyl-CoA (Fig 4 and Table G in S2 Appendix). Using Raman microspectroscopy applied to individual MMB, we demonstrated the presence of PHB and lipids, along with Nile Red staining of carbon-rich droplets within cells (S7 Fig and Table H in S2 Appendix). This is, to our knowledge, the first time carbon and energy storage compounds in MMB have been unambiguously identified. Carbon storage has been shown to support the multicellular reproductive life cycles in *Vibrio splendidus* through the specialization of cells during resource limitations [55], suggesting that MMB may utilize a similar mechanism to support their multicellular growth.

Altruistic behavior in biological systems is often favored when relatedness among species is high and the benefit is comparatively large compared to the cost, as has been observed in multicellular myxobacteria [46]. The SCMs revealed that MMB encode *mazE/F*, *hicA/B*, and *yefM/yefB* type II toxin-antitoxin (TA) systems (Fig 4 and Table G in S2 Appendix). TA systems represent an extreme example of altruism in multicellular systems, as individual cells that contribute to the organism by sacrificing themselves through death do not directly benefit from the organism's multicellularity. But, selection favoring altruistic traits occurs due to the fitness benefits those traits impart on relatives [56]. Detection of CRISPR (clustered regularly interspaced short palindromic repeats) systems I, III-A, and III-B (Table G in S2 Appendix) suggest the TA systems could be used in response to viral infection [57]. The evolution of altruistic cooperation in multicellular organisms has been proposed as a response to environmental stressors [56], indicating the presence of TA systems likely confers increased fitness for MMB in the environment.

## Cell-to-cell adhesion

One of the most intriguing features of MMB is their multicellular life cycle. But how these bacteria maintain their multicellular shape is not entirely known. Previous genomic and microscopic analysis of MMB suggested that exopolysaccharides, adhesion molecules, and Type IV pili could be involved in cell-to-cell adhesion [22,58]. Extracellular matrices, specifically those composed of polysaccharides, have been shown to be important for the development and maintenance of bacterial multicellularity, resulting in several emergent properties that benefit the organism, including the reduction of maintenance energy for individual cells [59]. *Myxobacteria* sp. and *Escherichia coli* have both been shown to use exopolysaccharides to maintain macroscopic biofilms [8,60]. The SCMs recovered in this study encode genes for extracellular polysaccharide biosynthesis, including family-2 glycosyltransferases (GT2), which have been shown to secrete diverse polysaccharides such as cellulose, alginate, and poly-N-acetylglucosamine [61,62]. Specifically, the genes identified in the SCMs were homologous to GT2 Bcs proteins, a bacterial protein complex that synthesizes and secretes a  $\beta$ -1,4-glucose polymer (e.g.,

cellulose) during biofilm formation (Table G in [S2 Appendix](#)) [63,64]. The LSSM MMB encode enzymes that catalyze the production of cellulose for biofilm formation (*bcsA*, *bcsQ*, *bcsZ*, *pilZ*, and *bglX*), but lack the co-organization of genes at a single locus as observed for other bacteria [63]. Furthermore, the *bcsB* and *bcsC* subunits were not identified, but additional GT2 as well as *wza* genes that may be involved in the synthesis of exopolysaccharides were present [65]. The catalytic activity of BcsA has been shown to be influenced by the concentration of cyclic dimeric guanosine monophosphate (c-di-GMP) which is in turn affected by environmental oxygen levels [66,67]. Under oxic conditions, the cellular level of c-di-GMP has been shown to increase and bind to BcsA, leading to increased cellulose synthesis [67]. Because MMB commonly exist in oxygen-deficient sediments, cellulose synthesis may be triggered under oxic conditions to stimulate biofilm formation, which has been observed in cultivation attempts of MMB [22].

Filamentous hemagglutinin has been shown to recognize and bind to carbohydrates to facilitate cell-to-cell adhesion in a biofilm [68,69]. The presence of filamentous hemagglutinin genes in our SCMs suggests MMB could use these protein complexes as a mechanism for cell-to-cell adhesion, as previously suggested [22]. Furthermore, the SCMs encode genes for OmpA/F porins, proteins with adhesive properties that have been suggested to interact with exopolysaccharides leading to aggregation of cells [70]. Type IV pili, which have been shown to be involved in cell-to-cell adhesion by interacting with exopolysaccharides [71], were also identified in the SCMs. The pili could alternatively be used for motility, chemotaxis, organization, and DNA uptake [72]. Further investigation into the use of the Type IV pili within MMB is warranted as only predictions can be made from the available genomes.

Previous studies on the membrane of MMB using Ruthenium Red dye and calcium cytochemistry have shown that the consortia are coated in a polysaccharide that extends between cells into the acellular central compartment but the exact composition and structure of this polysaccharide remains unclear [18,58]. Using Raman microspectroscopy, we identified peaks corresponding to exopolysaccharides, confirming the presence of an exopolysaccharide within or surrounding MMB (confocal Raman does not have enough z-resolution to distinguish the in- and out-side of cells; [S7 Fig](#) and Table H in [S2 Appendix](#)). Cellulase hydrolysis of the MMB resulted in eroded surfaces of the consortia, demonstrating that MMB are indeed covered by a cellulose layer ([S8 Fig](#)). Together, these analyses highlight the structural and functional significance of exopolysaccharides required for the multicellular morphotype of MMB.

### Abundance, distribution, and in situ activity of MMB in LSSM


Temporal shifts in MMB groups at LSSM have previously been documented [73] but the abundance of MMB correlated to sediment depth has not yet been analyzed. MMB in the LSSM subsurface were quantified by retrieving a 15-cm core from the tidal pond and determining the fractional abundance of each of the 5 MMB groups recovered throughout the core at centimeter-scale resolution using newly designed FISH probes ([S9 Fig](#) and Table I in [S2 Appendix](#)). In the top 5 centimeters of sediment, Group 1 MMB accounted for >75% of all MMB while the other groups accounted for 1% to 25%, depending on sediment depth. The total abundance of MMB dropped sharply below 5 cm, where the sediment horizons transitioned from sandy to dense clay sediment containing plant roots. This could be due to MMBs preference for low oxygen conditions, under which sulfate reduction is favored [39,74]. A similar depth-abundance profile was previously observed for the closely related MMB *Ca. M. multicellularis* [74].

BONCAT was used to determine the anabolic activity of MMB Group 1 in the top 6 cm of the LSSM core, which hosted the majority of MMB. Using this approach, we identified a statistically significant difference in MMB activity from 1 cm depth compared to the 2 to 3 cm

( $p < 3.4 \times 10^{-4}$ ) and from 3 cm compared to 4 to 5 cm ( $p < 3.9 \times 10^{-3}$ ), below which the MMB population diminished (S10 Fig). The increase of activity of MMB in the first 5 cm of the sediment could be attributed to the circumneutral pH and low redox potential (−260 to −460 mV), as previously observed to be important for the bioavailability of iron and sulfur species for MMB [40].

### Physiology of MMB

Previous genome- and chemotaxis-based studies suggested that MMB live by heterotrophic sulfate reduction using small organic acids as electron donors [22,39,40]. However, no direct observation of the use of such organics has been reported. Our metabolic reconstructions revealed that all MMB species in LSSM are genetically capable of coupling sulfate reduction to the use of acetate, propionate, and succinate as well as inorganic carbon fixation via the reductive acetyl-CoA pathway. To test whether MMB use these carbon sources to support their growth, we incubated sediment samples with  $^{13}\text{C}$ -labeled substrates (acetate, bicarbonate, propionate, and succinate) in situ and analyzed individual MMB using NanoSIMS. Consistent with metabolic predictions, MMB took up all  $^{13}\text{C}$ -labeled substrates (Fig 5 and Table J in S2 Appendix). To identify specific MMB groups, FISH was performed prior to NanoSIMS analyses. Group 1 MMB showed the highest incorporation of  $^{13}\text{C}$  from acetate as compared to Groups 3 and 4 ( $p < 1.5 \times 10^{-3}$ , S11 Fig). We also observed a significant difference between Group 1 and 4 for  $^{13}\text{C}$ -bicarbonate and  $^{13}\text{C}$ -propionate uptake ( $p < 3.9 \times 10^{-3}$  and  $5.8 \times 10^{-5}$ , respectively). At least 3 genera of MMB (i.e., Groups 1–3) assimilated both bicarbonate and



**Fig 5. NanoSIMS analysis of the cellular  $^{13}\text{C}$ -content of MMB consortia after in situ incubation with isotopically light or heavy carbon sources, specifically  $1,2\text{-}^{13}\text{C}_2$ -acetate,  $^{13}\text{C}$ -bicarbonate,  $1,2\text{-}^{13}\text{C}_2$ -propionate, or  $1,2\text{-}^{13}\text{C}_2$ -succinate, for 24 h.** The kill control contained magnetically enriched MMB that had been fixed in 4% paraformaldehyde prior to  $^{13}\text{C}$ -acetate addition. The negative control was sediment containing MMB without substrate addition. The dotted line shows the natural abundance of  $^{13}\text{C}$ . For further description of boxplots, see S1 Appendix. Inset images show representative NanoSIMS HSI for each  $^{13}\text{C}$ -labeled substrate analyzed. Color scales in HSI images are 1.1%–5% atom percent  $^{13}\text{C}$ . Scale bars are 5  $\mu\text{m}$ . S1C and S1D Fig show the incubation setup. For a comparison of the anabolic activity of MMB groups 1, 3, and 4, see S11 Fig. S12 Fig provides an example for correlative microscopy analysis of MMB. SI Materials and Methods detail the calculation of atom percent. The data underlying this figure can be found in Table J in S2 Appendix. For ROIs, see S13 Fig. HSI, hue saturated image; MMB, multicellular magnetotactic bacteria; NanoSIMS, nano-scale secondary ion mass spectrometry.

<https://doi.org/10.1371/journal.pbio.3002638.g005>


propionate (S15 Fig). We were unable to magnetically enrich MMB from a sediment sample incubated with  $^{13}\text{C}$ -acetate and molybdate, an inhibitor of sulfate reduction, indirectly demonstrating that MMB are in fact sulfate reducers. In summary, our analyses demonstrated that LSSM MMB are capable of assimilating both inorganic and organic carbon, indicating autotrophic and heterotrophic growth, and that different groups of MMB demonstrate variable affinities for carbon sources.

### Metabolic differentiation as studied by SIP-NanoSIMS

A hallmark of multicellularity is the existence of a division of labor [6,12]; however, because of their recalcitrance to cultivation, this hypothesis has never been addressed in MMB. Lacking a culture of MMB and established molecular techniques, such as mRNA-FISH, makes confirming a division of labor within this organism's consortium challenging. To address the existence of a division of labor within MMB, we investigated whether consortium members are metabolically differentiated by performing in vitro incubations of a magnetic enrichment of MMB with  $^{13}\text{C}$ -labeled acetate and deuterium oxide ( $^2\text{H}_2\text{O}$ ), as cellular labeling from the latter is a general proxy for metabolic activity [75]. Samples analyzed using NanoSIMS showed variation of isotopic signal across cells within individual consortia, indicating different metabolic activity within MMB (Fig 6 and Table K in S2 Appendix). The mass ratio for each isotope label was quantified and areas of high anabolism (referred to as "hotspots") within the consortium compared to the value of the same isotope label for the whole consortium. This analysis demonstrated a statistically significant difference of anabolic activity between hotspots and the whole consortium for both  $^{13}\text{C}$  and  $^2\text{H}_2\text{O}$  ( $p < 1.3 \times 10^{-3}$  and  $< 5.2 \times 10^{-9}$ , respectively). Comparison of SEM and NanoSIMS imaging shows that the extent of SIP labeling varies between single cells as well as across the entire MMB consortium (S12 Fig). The hotspots do not exhibit localization in any specific region of an MMB. However, they are not uniformly distributed throughout the consortium, demonstrating variations in metabolic activity with some areas displaying lower metabolic activity than others. To further investigate the localization of the isotope within the individual consortium, we applied a median filter ratio to the hue saturated images (HSIs) using different kernel radii [76]. This method averages the isotopic ratio over the given pixel radius, revealing sub-consortium localization across the MMB (S15 Fig). Together, our analyses show that metabolism of  $^{13}\text{C}$ -acetate and  $^2\text{H}$ -water is not uniform across the MMB, suggesting a differentiation in metabolic activity within individual consortia. Similar differences in the uptake of isotope-labeled substrate have also been reported for cellularly and metabolically differentiated cells of filamentous cyanobacterium *Anabaena oscillarioides* [77].

### Metabolic differentiation as studied by BONCAT


To determine if protein synthesis was localized to specific or individual cells within the consortium, we combined BONCAT with confocal laser scanning microscopy. Our analysis revealed an apparent gradient of newly synthesized proteins within each cell of the consortium, showing localization around the acellular center of individual consortia (Fig 7). This distinct pattern of protein synthesis was observed in all 57 MMB examined (S16 Fig) with negative controls showing no fluorescence (S17 Fig). The localization of newly synthesized protein around the acellular center of the consortium suggests this area is highly active; however, the reason is currently unknown. Cells within the consortium could engage in a division of labor by metabolizing specific substrates (e.g., acetate) and then sharing those resources with other cells through the acellular space, possibly by the utilization of membrane vesicles [58]. A prime example of a division of labor in multicellular bacteria is the filamentous cyanobacteria *Anabaena*. This organism has established a mutually beneficial interaction between the heterocyst and vegetative



**Fig 6. NanoSIMS analysis of MMB consortia incubated with 1,2- $^{13}\text{C}_2$ -acetate and  $^2\text{H}_2\text{O}$ .** To avoid human bias, ROIs for hotspots within individual consortia were auto-segmented in ImageJ and the isotope ratios of hotspots compared to the value for the whole consortium and negative controls. The  $^{13}\text{C}$  and  $^2\text{H}$  hotspots showed significantly higher isotopic enrichment when compared to the values for the respective whole consortium ( $p < 1.3 \times 10^{-3}$  and  $< 5.2 \times 10^{-9}$ , respectively), indicating they are metabolically differentiated. For further description of boxplots, see S1 Appendix. NanoSIMS HSI images of the same MMB consortia analyzed using mass ratio  $^{13}\text{C}^{12}\text{C}/^{12}\text{C}_2$  and  $^2\text{H}/^1\text{H}$ , revealing cell-to-cell differentiation. The HSI are scaled to show the atom percent of the respective isotope. Scale bars in HSI images equal 5  $\mu\text{m}$ . For an example of the correlative microscopy workflow used to study MMB, see S12 Fig. The data underlying this figure can be found in Table K in S2 Appendix. For ROIs of all consortia, see S14 Fig. Statistical analyses were performed using a pairwise  $t$  test with the Bonferroni  $p$ -adjusted method. HSI, hue saturated image; MMB, multicellular magnetotactic bacteria; NanoSIMS, nano-scale secondary ion mass spectrometry.

<https://doi.org/10.1371/journal.pbio.3002638.g006>

cells via intercellular exchange of metabolites through septal junctions [6,78]. However, there is no evidence that such pores or channels exist in MMB, although an alternative route for metabolite transfer could be the acellular space within the consortium. This space has been hypothesized to be used for communication and metabolite exchange because it provides the shortest distance between any 2 cells [58]. The localization of newly synthesized protein around the acellular center of the consortium suggests this area is highly active, possibly for exchange of metabolites from



**Fig 7. Heterogeneity in anabolic activity within individual MMB consortia as revealed by BONCAT.** (A) The averaged intensity profile across the diameter of 57 rotationally averaged BONCAT-labeled MMB with standard deviation shown in gray. RFI and diameter of each MMB was scaled as a ratio (0 to 1) to account for differences in fluorescence intensity between consortia and size of consortia. The boxplots show the averaged RFI for each quarter section of the radius with a pairwise statistical difference of  $p < 1.0 \times 10^{-10}$ . For further description of boxplots, see [S1 Appendix](#). (B) Gray scale confocal microscopy image of a BONCAT-labeled MMB showing proteins that had been synthesized over a 24-h period. (C) Image of the MMB shown in (B) that has been rotationally averaged prior to quantification in Eman2. The red dotted line shows each quarter analyzed for the boxplots shown in (A). For raw and rotationally averaged images of all 57 MMB, see [S16 Fig](#). Statistical analyses were performed using a pairwise *t* test with the Bonferroni *p*-adjusted method. The data underlying this figure can be found in Table L in [S2 Appendix](#). BONCAT, bioorthogonal noncanonical amino acid tagging; MMB, multicellular magnetotactic bacteria; RFI, relative fluorescence intensity.

<https://doi.org/10.1371/journal.pbio.3002638.g007>

cells that are hotspots for anabolic activity. This implies cells within the consortium could metabolize specific substrates (e.g., acetate) and then share those resources with other cells through the acellular space, possibly by the utilization of membrane vesicles [58].

## Conclusions

In summary, our study demonstrated that cutting-edge culture-independent approaches can reveal fundamental biology of yet uncultured multicellular microorganisms. We showed that MMB exhibit a higher level of complexity than previously thought by maintaining genomic heterogeneity and metabolic differentiation among the individual cells of a consortium. Moreover, we provided a detailed analysis of the genetic potential of 8 newly discovered species of MMB as well as their ecology, ecophysiology, and in situ activity. We hope that these results will eventually lead to MMB representatives being brought into culture. In addition, our results provide the basis for future experiments to further explore the mechanisms of cell-to-cell heterogeneity. Specifically, we expect mRNA-FISH [79,80] studies to reveal to what extent gene

expression levels differ from cell to cell, and SIP-NanoSIMS and spatial metabolomics [81] to reveal the molecular underpinnings of cellular interactions. Modeling approaches could shed light on potential metabolic networks within the consortium, further supporting the hypothesis of a division of labor. Additionally, such approaches could enable a deeper understanding of the propagation and constraints on genomic diversity observed within individual MMB consortia. Given that the biology of MMB is, as far as we know, unique in the bacterial domain, we propose MMB should, despite their recalcitrance to cultivation, receive higher attention by researchers interested in the evolution and biology of bacterial multicellularity.

## Materials and methods

### MMB sorting, single consortia genomic sequencing, and clonality analyses

A sediment sample from LSSM was shipped overnight to the Joint Genome Institute (JGI, then Walnut Creek, California, USA) where a magnetic enrichment was performed to obtain a pellet of MMB (see [S1 Appendix Methods](#) for details). The sample was stained with the DNA-stain SYBR Green (Thermo Fisher, Eugene, Oregon, USA) and large, fluorescent particles sorted using a BD Influx fluorescence-activated cell sorter (448 nm excitation of SYBR versus side scatter; [S18 Fig](#)) to obtain individual MMB consortia in single wells of a 384-well plate. In addition, replicates of 10, 30, 60, and 100 cells from a culture of *Pseudomonas putida* KT2440 that had been grown in LB media were sorted into single wells as a mock control for clonal multicellularity. The *P. putida* culture liquid culture was initiated from a single colony picked from an LB agar plate. Sorted MMB and *P. putida* were then lysed and DNA amplified via the WGA-X protocol [82]. Amplified SCMs were screened using 16S rRNA gene PCR according to DOE JGI standard protocols [83]. Next, sequencing libraries were generated from amplified DNA using the Nextera XT v2 library preparation kit (Illumina) and sequenced on the Illumina NextSeq platform. Assemblies were derived from the IMG/M database [84]. Contigs larger than 2 kb were organized into genome bins based on tetranucleotide sequence composition with MetaBat2 [85] with default settings. Metagenome assembled genome (MAG) completeness and contamination were estimated with CheckM (v1.012) [86]. Gene calling was performed with Prodigal [87] using the bacterial code (translation table 11). Average nucleotide identities (ANI) between MAGs were calculated with FastANI (v1.1) [88], filtered at 95% sequence identity and 30% aligned fraction, and then clustered using mcl (v14-137) [89].

We assessed clonality of sorted MMBs, single sorted and amplified *Pseudomonas* controls and other MAGs derived from sorted MMBs by mapping the reads from the respective libraries to the contigs larger than 5 kb in assemblies derived from the same library using BBMap (v38.79) (<https://sourceforge.net/projects/bbmap/>, [90]) with the flags `minid = 0.95 minaveragequality = 30`. Variants were called with the BBTools script `callvariants.sh` using the flags `minreads = 2 minquality = 30 minscore = 30 minavgmapq = 20 minallefrac = 0.05` and identified variants were then annotated as synonymous (s), nonsynonymous (ns), or intergenic depending on their position. Variants made up by one or more Ns were excluded from the analysis. To investigate differences between MMB, all libraries were also mapped to contigs with a size of at least 5 kb from the longest MMB assembly (3300034493).

### Stable isotope probing

To empirically test the use of carbon substrates as predicted by the functional annotation of MMB SCMs and determine the anabolic activity of MMB cells, we performed both in situ and in vitro incubations of MMB with  $^{13}\text{C}$ - and  $^2\text{H}$ -labeled substrates (all 99.9%, Cambridge Isotopes Laboratories). The in situ incubations were performed in duplicate on August 28, 2022 at LSSM by amending 200 ml top sediment slurry with 2 mM  $^{13}\text{C}$ -1,2-acetate, 2 mM  $^{13}\text{C}$ -

1,2-succinate, 5 mM  $^{13}\text{C}$ -1,2-propionate, 5 mM  $^{13}\text{C}$ -bicarbonate, or 2 mM  $^{13}\text{C}$ -1,2-acetate plus 8 mM molybdate (a competitive inhibition of sulfate reduction). A negative control to which no amendment was made as well as a killed control in which biomass had been preincubated with 4% paraformaldehyde (PFA) for 60 min at ambient temperature prior to addition of 2 mM  $^{13}\text{C}$ -1,2-acetate were also performed. Samples were stored in 200 ml Pyrex glass bottles (Corning, Glendale, Arizona, USA) and incubated for 24 h in situ at the sample site where they were buried 4 to 6 cm below the sediment in a basket (S1C and S1D Fig). The in vitro incubations were performed by incubating magnetically enriched MMB in 10 ml of 0.22  $\mu\text{m}$  filter sterilized (Millipore, Burlington, Massachusetts, USA) LSSM water amended with the same amendments as the in situ incubations, as well as 50% deuterium oxide ( $\text{D}_2\text{O}$ ), for 24 h at ambient lab temperature (approximately 23°C) in the dark. At the end of each incubation period, MMB were magnetically enriched and fixed with 4% PFA for 60 min at ambient temperature. Cells were centrifuged for 5 min at 16,000 g, after which the supernatant was removed, and the cell pellets resuspended in 50  $\mu\text{l}$  1 $\times$  PBS and stored at 4°C.

### NanoSIMS

Samples were prepared for NanoSIMS on stainless steel coupons as previously described [91]; for details, see SI [Materials and Methods](#). To quantify cell-to-cell differences in isotope uptake within individual consortia, ROIs were selected around localized densities (i.e., hotspots) of masses corresponding to the respective substrate and compared to whole consortia values for the same isotope of interest. In order to not introduce human bias, ROIs were selected in Fiji (<https://imagej.net/software/fiji/>) by converting the mass image to an 8-bit image for which the brightness and contrast adjusted to help identify the localized densities for the mass of interest (e.g.,  $^{12}\text{C}^{2}\text{H}$  14.02,  $^{12}\text{C}^{13}\text{C}$  25.00) using the thresholding functions within the software.

### BONCAT

BONCAT was performed as previously described [92]; for details, see SI [Materials and Methods](#). To evaluate cell-cell differences in anabolic activity of individual consortia, MMB were imaged by taking z-stacks (approximately 300 nm per image) of the entire consortia using an Inverted DMI8 Stellaris 8 Confocal Microscope (Leica Microsystems). Images focused on the center of the consortia were selected and Eman2 [93] was used to select individual MMB for particle analysis. Each image was then filtered using an edge mean normalization, center of mass xform, and rotational average math settings (S16 Fig). Because of varying sizes of consortia, a Python script was used to determine the radius of each consortium by calculating the number of pixels from the center of mass, as determined by the filter, to where the standard deviation of the pixels is <0.01. The radius of all consortia was standardized by dividing 1 by the radius. Additionally, the average fluorescence intensity was normalized by calculating  $I_{norm} = \frac{I_{ori} - I_{min}}{I_{max} - I_{min}}$ , where  $I_{ori}$  is the original fluorescence intensity value and  $I_{min}/I_{max}$  are the minimum and maximum relative fluorescence intensity (RFI) values for the individual consortia. The average and standard deviation of data was calculated and plotted using R. All code used for analysis is deposited on GitHub (<https://github.com/georgeschaible/MMB-BONCAT>).

### Supplementary methodology

Sample collection, phylogenetic analysis, genome and magnetosome analyses, FISH, BONCAT, NanoSIMS, Raman microspectroscopy, and SEM experiments, geochemical analysis, and statistical analyses are described in the SI [Materials and Methods](#).



## Supporting information

**S1 Fig. Little Sippewissett salt marsh, Falmouth MA.** (A) Photo of the tidal pool from which sulfidic sediments were obtained, facing west towards Buzzards Bay. (B) Map of the salt marsh showing the tidal pool in red and water in white. (C) Each sample was incubated in a 200 ml bottle filled to the top with the sediment slurry and tightly capped. Because no MMB could be recovered post-fixation from the kill control sample, 200  $\mu$ l of sample were incubated in a small glass vial inside of the 200 ml bottle. (D) Samples were incubated in situ below the sediment at the site for 24 h. All photos were taken by George A. Schaible. Base layer of map made using USGS topographical map (<https://www.sciencebase.gov/catalog/item/5b3cb9eee4b060350a0a9ae2>). (PDF)

**S2 Fig. Phylogenetic analysis of MMB using near-full length 16S rRNA genes (length listed next to name) found in 14 of the 22 SCMs and in reference genomes.** Tree reconstructed using maximum likelihood method with bootstrap values calculated using 500 replicates. Bootstrap values above 50 are shown. *Ca. M. abreuianus* is not shown in this analysis because no 16S rRNA gene was recovered from the SCM. Color coded sequences belong to their respective SCM, as shown in Table A in [S2 Appendix](#). Bars on right show specificities of our newly designed FISH probes that target genus-level groups of MMB in LSSM (Table I in [S2 Appendix](#)). (PDF)

**S3 Fig. Near-full length 16S rRNA gene comparison of all sequences recovered in this study and previous studies at LSSM (Simmons and Edwards, 2007).** Percent identity values are shown within boxes. Bars on left highlight MMB groups for which genus-level FISH probes designed (Table I in [S2 Appendix](#)). (PDF)

**S4 Fig. Near-full length 16S rRNA identity comparison for the 14 sequences recovered from SCMs and the 2 MMB reference genomes (*Ca. M. multicellularis* and *Ca. Magnetomorum* sp. HK-1).** Percent identity values are shown within boxes. (PDF)

**S5 Fig. Genome ANI comparing each of the 22 individual SCMs with the 2 publicly available reference genomes (*Ca. M. multicellularis* and *Ca. Magnetomorum* sp. HK-1).** ANI values are shown within boxes. (PDF)

**S6 Fig. Heatmap and cluster analysis of pfams annotation of individual SNPs showing the log<sub>2</sub> ratio of non-synonymous to synonymous substitutions (dN/dS) for the SNP differences contained within each SCM.** The analysis suggested that most genes were subject to negative (purifying) selection. On the other hand, genes without functional annotation (“no hits”) were frequently subject to positive selection. The data underlying this figure can be found in Table F in [S2 Appendix](#). (PDF)

**S7 Fig. Representative Raman spectrum of an MMB using a 532 nm laser.** Vertical lines show peaks corresponding to polyhydroxybutyrate (blue), triglycerides (gold), and exopolysaccharides (pink). Wavenumbers corresponding to peaks are listed in Table F in [S2 Appendix](#). The large peak at approximately 335  $\text{cm}^{-1}$  is assigned to the magnetosome crystal greigite, which has previously been shown for MMB from the same site (Schaible and colleagues). Inset image shows an MMB consortium stained with Nile Red, indicating C-H rich droplets within

cells. The contrast and brightness of the image has been increased for better visualization. Scale bar is 5  $\mu\text{m}$ .

(PDF)

**S8 Fig. Cellulase treatment of MMB.** (A1-3) Control sample of MMB incubated without cellulase. (B1-3) After treatment with cellulase the surface of MMB consortia was noticeably eroded as compared to the control. Both samples were incubated for 1 h under otherwise identical conditions (pH, temperature, and osmolarity). All scale bars are 1  $\mu\text{m}$ .

(PDF)

**S9 Fig. Fractional abundance of MMB groups by depth in LSSM.** (A) Image of the 15 cm core taken from the West end of sampling site prior to being sectioned into 1 cm horizons from which MMB were enriched for quantification by FISH. (B) DOPE-FISH analysis of MMB Groups 2 (red) and 5 (green) shown in panel (B) and Groups 1 (green), 3 (yellow), and 4 (red) shown in panel (C). MMB not detected by the respective FISH probes are shown in the blue DAPI counterstain in the microscopy images. Scale bars are 5  $\mu\text{m}$ . Bar plots show the abundance of each MMB group as determined by DOPE-FISH for each centimeter of the sediment core shown in panel (A). Unlabeled populations are MMB that were stained with DAPI but were not detected by the FISH probes used in the 2 separate experiments and are shown in gray. Consistent with results from SCM and previous 16S rRNA gene abundance studies (Simmons and Edwards, 2007) in LSSM, Group 1 numerically dominate the MMB population. FISH probes used in this experiment are detailed in Table I in [S2 Appendix](#). Statistical analyses were performed using a pairwise *t* test with the Bonferroni *p*-adjusted method. The data underlying this figure can be found in Table P in [S2 Appendix](#). Photo by George Schaible.

(PDF)

**S10 Fig. Anabolic activity of MMB inhabiting the top 6 cm of LSSM sediment as measured by BONCAT.** (A) 1 cm sediment core horizons were incubated in the presence of the methionine analogue HPG and magnetically enriched MMB stained via azide-alkyne click chemistry with Alexa Fluor 405 to show relative activity of Group 1 MMB as a factor of depth in the sediment. The vertical line within each box shows the median and the whisker shows the range of the data. Dots represent individual MMB that were measured and analyzed using the software package Daime. Data points that were more than 2 standard deviations of the mean are shown as individual points past the whicker. The analysis showed that there is a statistically relevant difference in the activity of MMB from 1 cm depth to 2 to 3 cm and again from 2 to 3 cm to the 4 to 5 cm depth. (B) Exemplary epifluorescence microscopy image of click-stained MMB. (C) Overlay epifluorescence microscopy image of FISH-labeled MMB shown in panel B.

Group 1 is shown in green, Group 3 in yellow, and Group 4 in red. All scale bars are 5  $\mu\text{m}$ . All statistically differences are shown: \*\* =  $p < 3.9 \times 10^{-3}$ , \*\*\* =  $p < 3.5 \times 10^{-4}$ . FISH probes used in this experiment are detailed in Table I in [S2 Appendix](#). Statistical analyses were performed using a pairwise *t* test with the Bonferroni *p*-adjusted method. The data underlying this figure can be found in Table Q in [S2 Appendix](#).

(PDF)

**S11 Fig. Comparison of  $^{13}\text{C}$ -labeled substrate incorporation by MMB Groups 1, 3, and 4 using NanoSIMS analysis of mass ratio  $^{13}\text{C}^{12}\text{C}/^{12}\text{C}_2$ .** The analysis shows that MMB in Group 1 anabolize acetate at a statistically greater rate than Groups 3 and 4 ( $p < 8.9 \times 10^{-3}$ ). Group 1 also incorporated more bicarbonate than Group 4 ( $p < 2.4 \times 10^{-2}$ ), although Group 4 only contained 4 samples to compare. Statistical analyses were performed using a pairwise *t* test with the Bonferroni *p*-adjusted method. The data underlying this figure can be found in

Table K in [S2 Appendix](#).  
(PDF)

**S12 Fig. Correlative imaging of MMB.** The (A) taxonomy (DOPE-FISH), (B) morphology (SEM), (C) distribution of sulfur (NanoSIMS, mass 32; a proxy for the presence of sulfur-containing magnetosomes), and (D) uptake of 1,2-<sup>13</sup>C<sub>2</sub>-labeled acetate (NanoSIMS, HSI image showing mass ratio <sup>13</sup>C<sup>12</sup>C/<sup>12</sup>C<sub>2</sub>). Scale bars are 5 μm. The HSI mass ratio color scale in (D) is 1.1%–5% atom percent.  
(PDF)

**S13 Fig. ROIs for NanoSIMS substrate analysis shown in Fig 5 of main text.** Because the in situ incubation incurred particles that were not of interest (e.g., diatoms and particulates), the ROIs were hand drawn around each MMB using the mass 26.00 (<sup>12</sup>C<sup>14</sup>N) channel to avoid incorporation of exogenous material in the analysis. (A1) <sup>13</sup>C-acetate, (A2) <sup>12</sup>C-acetate, (B1) <sup>13</sup>C-bicarbonate, (B2) <sup>12</sup>C-bicarbonate, (C1) <sup>13</sup>C-propionate, (C2) <sup>12</sup>C-propionate, (D1) <sup>13</sup>C-succinate, (D2) <sup>12</sup>C-succinate, (E) <sup>13</sup>C-acetate kill control, (F) negative control. ROIs are shown in green and red outlines.  
(PDF)

**S14 Fig. ROIs for NanoSIMS hotspot analysis shown in Fig 6 of main text.** As to avoid introducing bias into the selection of hotspot ROIs, thresholding in ImageJ was used to automatically select for ROIs, as outlined in the methods. The respective mass image was used for hotspot thresholding and ROI selection. ROIs for whole consortia were hand drawn. All ROIs are shown in red outlines.  
(PDF)

**S15 Fig.** Median filter ratio radius effect on HSI NanoSIMS images of <sup>13</sup>C and <sup>2</sup>H hotspots (A–C) Mass ratio (<sup>2</sup>H<sup>12</sup>C/<sup>1</sup>H<sup>12</sup>C) of MMB labeled with deuterium oxide (<sup>2</sup>H<sub>2</sub>O). (D–F) Mass ratio (<sup>13</sup>C<sup>12</sup>C/<sup>12</sup>C<sub>2</sub>) of the same MMB shown in (A–C) but labeled with 1,2-<sup>13</sup>C<sub>2</sub>-labeled acetate. For these images, the median filter ratio radius was increased to show the effect of noise reduction and localization of isotope label within consortia. A higher filter radius reveals isolated areas of the respective isotope label within MMB, though for a radius >5, the label is averaged over an area greater than the size of a single cell within the consortium, thus losing cellular resolution. Independent of the radius chosen, hot spots remain visible.  
(PDF)

**S16 Fig. Anabolic activity within individual consortia.** (A) Gray-scale images of individual MMB stained via azide-alkyne click chemistry with Alexa Fluor 488. (B) The same consortia shown in (A) that have been rotationally averaged in Eman2 software. The relative fluorescence intensity was standardized for all samples prior to analysis.  
(PDF)

**S17 Fig. Controls for metabolic differentiation as studied by BONCAT.** (A) AHA positive BONCAT *E. coli* control. (B) AHA negative BONCAT *E. coli* control. (C) AHA positive BONCAT of MMB. (D) AHA negative BONCAT of MMB. (E) The exposure time was adjusted to allow for visualization of the AHA negative MMB from panel (D), which resulted in a dramatic over exposure (F) of the AHA positive MMB from panel (C).  
(PDF)

**S18 Fig. Fluorescence activated cell sorting of a magnetically enriched sample from tidal pond sediment stained with SYBR Green.** A sorting gate, presumed to contain MMB consortia, was set around particles with a strong 488 nm signal and high side scatter (SSC), indicating

a large cell size. Other particles likely are single-cell magnetotactic bacteria or non-magnetotactic bacteria present in the pond water. MMB consortia were sorted into individual wells of a microtiter well plate and 22 MMB consortia were genome sequenced.

(PDF)

**S19 Fig. Gene synteny for scaffolds containing the magnetosome gene clusters compared.**

The corresponding annotations of colored genes are shown in the legend to the right.

(PDF)

**S1 Appendix. Supporting Results, Discussion, and Materials and Methods.**

(DOCX)

**S2 Appendix. Supplementary tables A–Q. Table A in S2 Appendix.** Genome features of SCM recovered from LSSM MMB as well as available reference genomes. **Table B in S2 Appendix.** List of accession numbers used for 16S rRNA phylogenetic analysis. **Table C in S2 Appendix.** Identification of common single copy genes across all SCMs and reference genomes used to make phylogenomic tree. Genes shown in green were used to construct the phylogenetic tree in Fig 2. **Table D in S2 Appendix.** List of researchers and location as well as etymologies for MMB species. **Table E in S2 Appendix.** Analysis of clonality within individual MMB. **Table F in S2 Appendix.** Analysis of synonymous versus non-synonymous mutations within SCMs. **Table G in S2 Appendix.** Metabolic pathway and functional annotations for SCMs from IMG annotations. Absence of gene in a specific SCM is denoted by a—symbol. Locus tag is listed for each gene present in SCM. **Table H in S2 Appendix.** Raman wavenumbers corresponding to biomolecules. **Table I in S2 Appendix.** List of FISH probes. All probes bind at positions 1032–1049 (using *E. coli* 16S rRNA as reference) and compete with each other for their binding site. See S9 Fig, S10 Fig, and S12 Fig for examples of FISH. **Table J in S2 Appendix.** NanoSIMS data for in situ experiments showing taxonomy via FISH as well as substrate amendments. **Table K in S2 Appendix.** NanoSIMS data for in vitro experiments comparing hotspots to whole consortium and controls. **Table L in S2 Appendix.** Relative radii and fluorescence intensity for BONCAT showing heterogeneity in anabolic activity within individual MMB consortia. Values determined using Eman2. **Table M in S2 Appendix.** Media recipe for cultivation of MMB. **Table N in S2 Appendix.** Water chemistry of LSSM sample site at 2 time points. Water collected above sediment during low tide. **Table O in S2 Appendix.** Comparative analysis of magnetosome genes using a BLAST of *Candidatus Desulfamplus magnetomortis* BW-1 magnetosome gene cluster genes against each SCM and the available reference genomes. **Table P in S2 Appendix.** Fractional abundance data for MMB groups analyzed by depth in LSSM for S9 Fig. Count adjusted (Corrected Count) for volume of original sample. **Table Q in S2 Appendix.** Relative fluorescence intensity calculations for BONCAT experiment shown in S10 Fig.

(XLSX)

**S1 Video. Third and final round of a magnetic enrichment of MMB.** MMB swim from the bottom of the microcentrifuge tube up towards the magnetic North of a magnetic stir bar.

Video is 30× the original speed.

(MOV)

**S2 Video. MMB swimming at the edge of a hanging water droplet towards the magnetic North of a magnetic stir bar that is out of frame.** The temporal response of MMB to changes in the magnetic field is observed when the magnet is turned. This switches the magnetic field and induces a change in the swimming direction of the MMB consortia, until the magnet is turned again, and the MMB swim back to the edge of the hanging water droplet. Video is at its

original speed.  
(MOV)

## Acknowledgments

We thank Jeffrey Marlow (Boston University), Rachel Spietz (MSU), and Ashley Cohen (MSU) for help with the collection of LSSM sediment samples and assistance with lab work as well as Heidi Smith (MSU) for microscopy support. We also thank Anthony Kohtz, Amanda Wilkins, and Hope McWilliams (all MSU) for assistance with lab work, Marike Palmer (University of Nevada Las Vegas) for discussions on taxonomy, Julie Huber (Woods Hole Oceanographic Institution) for graciously providing access to her lab space at WHOI, and Kristina Hillesland (University of Washington, Bothell) for critical comments that helped to improve the manuscript. We thank our Brazilian colleagues Fernanda Abreu, Henrique Lins de Barros, Marcos Farina, Carolina Keim, and Juliana Martins (Lopez), as well as Sherri Simmons for their foundational work on MMB and allowing us to name newly discovered MMB species after them and in honor of the late Ulysses Lins, who transformed our understanding of MMB.

## Author Contributions

**Conceptualization:** George A. Schaible, Roland Hatzenpichler.

**Data curation:** George A. Schaible, Zackary J. Jay, John Cliff, Frederik Schulz.

**Formal analysis:** George A. Schaible, Zackary J. Jay, John Cliff, Frederik Schulz, Colin Gauvin, Roland Hatzenpichler.

**Funding acquisition:** George A. Schaible, Roland Hatzenpichler.

**Investigation:** George A. Schaible, Zackary J. Jay, John Cliff, Frederik Schulz, Danielle Goudeau, Rex R. Malmstrom, S. Emil Ruff, Virginia Edgcomb, Roland Hatzenpichler.

**Methodology:** George A. Schaible, Zackary J. Jay, John Cliff.

**Project administration:** Roland Hatzenpichler.

**Resources:** George A. Schaible, Roland Hatzenpichler.

**Supervision:** Roland Hatzenpichler.

**Validation:** George A. Schaible, Zackary J. Jay, John Cliff, Roland Hatzenpichler.

**Visualization:** George A. Schaible, Frederik Schulz, Colin Gauvin, Roland Hatzenpichler.

**Writing – original draft:** George A. Schaible, Roland Hatzenpichler.

**Writing – review & editing:** George A. Schaible, Zackary J. Jay, John Cliff, Frederik Schulz, Roland Hatzenpichler.

## References

1. Kaiser D. Building a multicellular organism. *Annu Rev Genet.* 2001; 35(1):103–123. <https://doi.org/10.1146/annurev.genet.35.102401.090145> PMID: 11700279
2. Grosberg RK, Strathmann RR. The Evolution of Multicellularity: A Minor Major Transition? *Annu Rev Ecol Evol Syst.* 2007; 38(1):621–654.
3. Niklas KJ, Newman SA. The origins of multicellular organisms. *Evol Dev.* 2013; 15(1):41–52. <https://doi.org/10.1111/ede.12013> PMID: 23331916

4. Umen J, Herron MD. Green algal models for multicellularity. *Annu Rev Genet.* 2021; 55:603–632. <https://doi.org/10.1146/annurev-genet-032321-091533> PMID: 34546795
5. Rokas A. The origins of multicellularity and the early history of the genetic toolkit for animal development. *Annu Rev Genet.* 2008; 42:235–251. <https://doi.org/10.1146/annurev.genet.42.110807.091513> PMID: 18983257
6. Claessen D, Rozen DE, Kuipers OP, Sogaard-Andersen L, van Wezel GP. Bacterial solutions to multicellularity: a tale of biofilms, filaments and fruiting bodies. *Nat Rev Microbiol.* 2014; 12(2):115–124. <https://doi.org/10.1038/nrmicro3178> PMID: 24384602
7. Brunet T, King N. The Origin of Animal Multicellularity and Cell Differentiation. *Dev Cell.* 2017; 43(2):124–140. <https://doi.org/10.1016/j.devcel.2017.09.016> PMID: 29065305
8. Chavhan Y, Dey S, Lind PA. Bacteria evolve macroscopic multicellularity by the genetic assimilation of phenotypically plastic cell clustering. *Nat Commun.* 2023; 14(1):3555. <https://doi.org/10.1038/s41467-023-39320-9> PMID: 37322016
9. Herron MD, Borin JM, Boswell JC, Walker J, Chen IK, Knox CA, et al. De novo origins of multicellularity in response to predation. *Sci Rep.* 2019; 9(1):2328. <https://doi.org/10.1038/s41598-019-39558-8> PMID: 30787483
10. Fisher RM, Regenberg B. Multicellular group formation in *Saccharomyces cerevisiae*. *Proc Biol Sci.* 1910; 2019(286):20191098.
11. Hammerschmidt K, Landan G, Tria FDKm, Alcorta J, Dagan T. The order of trait emergence in the evolution of cyanobacterial multicellularity. *Genome Biol Evol.* 2020:13.
12. Geerlings NMJ, Karman C, Trashin S, As KS, Kienhuis MVM, Hidalgo-Martinez S, et al. Division of labor and growth during electrical cooperation in multicellular cable bacteria. *Proc Natl Acad Sci U S A.* 2020; 117(10):5478–5485. <https://doi.org/10.1073/pnas.1916244117> PMID: 32094191
13. Mizuno K, Maree M, Nagamura T, Koga A, Hirayama S, Furukawa S, et al. Novel multicellular prokaryote discovered next to an underground stream. *elife.* 2022:11.
14. Abreu F, Martins JL, Silveira TS, Keim CN, de Barros HG, Filho FJ, et al. 'Candidatus Magnetoglobus multicellularis', a multicellular, magnetotactic prokaryote from a hypersaline environment. *Int J Syst Evol Microbiol.* 2007; 57(Pt 6):1318–1322. <https://doi.org/10.1099/ijs.0.64857-0> PMID: 17551050
15. Keim CN, Martins JL, Abreu F, Rosado AS, de Barros HL, Borojevic R, et al. Multicellular life cycle of magnetotactic prokaryotes. *FEMS Microbiol Letters.* 2004; 240(2):203–208. <https://doi.org/10.1016/j.femsle.2004.09.035> PMID: 15522508
16. Keim CN, Farina M, Lins U. Magnetoglobus, Magnetic Aggregates in Anaerobic Environments. *Microbe.* 2007; 2:437–445.
17. Leao P, Chen YR, Abreu F, Wang M, Zhang WJ, Zhou K, et al. Ultrastructure of ellipsoidal magnetotactic multicellular prokaryotes depicts their complex assemblage and cellular polarity in the context of magnetotaxis. *Environ Microbiol.* 2017; 19(6):2151–2163. <https://doi.org/10.1111/1462-2920.13677> PMID: 28120460
18. Abreu F, Silva KT, Leao P, Guedes IA, Keim CN, Farina M, et al. Cell adhesion, multicellular morphology, and magnetosome distribution in the multicellular magnetotactic prokaryote *Candidatus Magnetoglobus multicellularis*. *Microsc Microanal.* 2013; 19(3):535–543. <https://doi.org/10.1017/S1431927613000329> PMID: 23551897
19. Chen YR, Zhang R, Du HJ, Pan HM, Zhang WY, Zhou K, et al. A novel species of ellipsoidal multicellular magnetotactic prokaryotes from Lake Yuehu in China. *Environ Microbiol.* 2015; 17(3):637–647. <https://doi.org/10.1111/1462-2920.12480> PMID: 24725306
20. Keim CN, Martins JL, de Barros HL, Lins U. Structure, behavior, ecology and diversity of multicellular magnetotactic prokaryotes. *Magnetoreception and magnetosomes in bacteria.* 2006 (Springer, Berlin, Heidelberg):103–32.
21. Teng Z, Zhang Y, Zhang W, Pan H, Xu J, Huang H, et al. Diversity and Characterization of Multicellular Magnetotactic Prokaryotes From Coral Reef Habitats of the Paracel Islands. *South China Sea Front Microbiol.* 2018; 9:2135.
22. Abreu F, Morillo V, Nascimento FF, Werneck C, Cantao ME, Ciapina LP, et al. Deciphering unusual uncultured magnetotactic multicellular prokaryotes through genomics. *ISME J.* 2014; 8(5):1055–1068. <https://doi.org/10.1038/ismej.2013.203> PMID: 24196322
23. Lefèvre CT, Bazylinski DA. Ecology, Diversity, and Evolution of Magnetotactic Bacteria. *Microbiol Mol Biol Rev.* 2013; 77(3):497–526. <https://doi.org/10.1128/MMBR.00021-13> PMID: 24006473
24. Qian X, Zhao Y, Santini C-L, Pan H, Xiao T, Chen H, et al. How light affect the magnetotactic behavior and reproduction of ellipsoidal multicellular magnetoglobules? *J Oceanol Limnol.* 2021; 39(6):2005–2014.

25. Qian XX, Santini CL, Kosta A, Menguy N, Le Guenno H, Zhang W, et al. Juxtaposed membranes underpin cellular adhesion and display unilateral cell division of multicellular magnetotactic prokaryotes. *Environ Microbiol.* 2020; 22(4):1481–1494. <https://doi.org/10.1111/1462-2920.14710> PMID: 31187926
26. Abreu F, Silva KT, Martins JL, Lins U. Cell viability in magnetotactic multicellular prokaryotes. *Int Microbiol.* 2006; 9:267–272. PMID: 17236160
27. Simmons SL, Edwards KJ. Unexpected diversity in populations of the many-celled magnetotactic prokaryote. *Environ Microbiol.* 2007; 9(1):206–215. <https://doi.org/10.1111/j.1462-2920.2006.01129.x> PMID: 17227425
28. Perantoni M, Esquivel DM, Wajnberg E, Acosta-Avalos D, Cernicchiaro G, Lins de Barros H. Magnetic properties of the microorganism *Candidatus Magnetoglobus multicellularis*. *Naturwissenschaften.* 2009; 96(6):685–690. <https://doi.org/10.1007/s00114-009-0520-2> PMID: 19283357
29. Winkelhofer M, Abracado LG, Davila AF, Keim CN, Lins de Barros HG. Magnetic optimization in a multicellular magnetotactic organism. *Biophys J.* 2007; 92(2):661–670. <https://doi.org/10.1529/biophysj.106.093823> PMID: 17071652
30. Almeida FP, Viana NB, Lins U, Farina M, Keim CN. Swimming behaviour of the multicellular magnetotactic prokaryote '*Candidatus Magnetoglobus multicellularis*' under applied magnetic fields and ultraviolet light. *Antonie Van Leeuwenhoek.* 2013; 103(4):845–857. <https://doi.org/10.1007/s10482-012-9866-0> PMID: 23242915
31. Shapiro OH, Hatzenpichler R, Buckley DH, Zinder SH, Orphan VJ. Multicellular photo-magnetotactic bacteria. *Environ Microbiol Rep.* 2011; 3(2):233–238. <https://doi.org/10.1111/j.1758-2229.2010.00215.x> PMID: 23761255
32. Greening C, Lithgow T. Formation and function of bacterial organelles. *Nat Rev Microbiol.* 2020; 18(12):677–689. <https://doi.org/10.1038/s41579-020-0413-0> PMID: 32710089
33. Taoka A, Eguchi Y, Shimoshige R, Fukumori Y. Recent advances in studies on magnetosome-associated proteins composing the bacterial geomagnetic sensor organelle. *Microbiol Immunol.* 2023; 67(5):228–238. <https://doi.org/10.1111/1348-0421.13062> PMID: 36892203
34. Bazylinski DA, Frankel RB. Magnetosome formation in prokaryotes. *Nat Rev Microbiol.* 2004; 2(3):217–230. <https://doi.org/10.1038/nrmicro842> PMID: 15083157
35. Keim CN, Martins JL, de Barros HL, Lins U, Farina M. Structure, behavior, ecology and diversity of multicellular magnetotactic prokaryotes. In *Magnetoreception and magnetosomes in bacteria*. Springer; 2007. p. 103–32.
36. Simmons SL, Bazylinski DA, Edwards KJ. Population dynamics of marine magnetotactic bacteria in a meromictic salt pond described with qPCR. *Environ Microbiol.* 2007; 9(9):2162–2174. <https://doi.org/10.1111/j.1462-2920.2007.01330.x> PMID: 17686015
37. Martins JL, Silveira TS, Silva KT, Lins U. Salinity dependence of the distribution of multicellular magnetotactic prokaryotes in a hypersaline lagoon. *Int Microbiol.* 2009; 12(3):193.
38. Lefevre CT, Abreu F, Lins U, Bazylinski DA. Nonmagnetotactic multicellular prokaryotes from low-saline, nonmarine aquatic environments and their unusual negative phototactic behavior. *Appl Environ Microbiol.* 2010; 76(10):3220–3227. <https://doi.org/10.1128/AEM.00408-10> PMID: 20363801
39. Wenter R, Wanner G, Schuler D, Overmann J. Ultrastructure, tactic behaviour and potential for sulfate reduction of a novel multicellular magnetotactic prokaryote from North Sea sediments. *Environ Microbiol.* 2009; 11(6):1493–1505. <https://doi.org/10.1111/j.1462-2920.2009.01877.x> PMID: 19220395
40. Kolinko S, Richter M, Glockner FO, Brachmann A, Schuler D. Single-cell genomics reveals potential for magnetite and greigite biomineralization in an uncultivated multicellular magnetotactic prokaryote. *Environ Microbiol Rep.* 2014; 6(5):524–531. <https://doi.org/10.1111/1758-2229.12198> PMID: 25079475
41. Cui K, Pan H, Chen J, Liu J, Zhao Y, Chen S, et al. A Novel Isolate of Spherical Multicellular Magnetotactic Prokaryotes Has Two Magnetosome Gene Clusters and Synthesizes Both Magnetite and Greigite Crystals. *Microorganisms.* 2022; 10(5). <https://doi.org/10.3390/microorganisms10050925> PMID: 35630369
42. Fisher RM, Cornwallis CK, West SA. Group formation, relatedness, and the evolution of multicellularity. *Curr Biol.* 2013; 23(12):1120–1125. <https://doi.org/10.1016/j.cub.2013.05.004> PMID: 23746639
43. Zhou K, Zhang WY, Yu-Zhang K, Pan HM, Zhang SD, Zhang WJ, et al. A novel genus of multicellular magnetotactic prokaryotes from the Yellow Sea. *Environ Microbiol.* 2012; 14(2):405–413. <https://doi.org/10.1111/j.1462-2920.2011.02590.x> PMID: 21978297
44. Chen H, Li J, Wu L-F, Zhang W-J. Morphological and phylogenetic diversity of magnetotactic bacteria and multicellular magnetotactic prokaryotes from a mangrove ecosystem in the Sanya River, South China. *J Oceanol Limnol.* 2021; 39(6):2015–2026.

45. Wielgoss S, Wolfensberger R, Sun L, Fiegna F, Velicer GJ. Social genes are selection hotspots in kin groups of a soil microbe. *Science*. 2019; 363(6433):1342–1345. <https://doi.org/10.1126/science.aar4416> PMID: 30898932
46. Velicer GJ, Vos M. Sociobiology of the myxobacteria. *Ann Rev Microbiol*. 2009; 63:599–623. <https://doi.org/10.1146/annurev.micro.091208.073158> PMID: 19575567
47. Kim W, Levy SB, Foster KR. Rapid radiation in bacteria leads to a division of labour. *Nat Commun*. 2016; 7:10508. <https://doi.org/10.1038/ncomms10508> PMID: 26852925
48. Borisov VB, Gennis RB, Hemp J, Verkhovsky MI. The cytochrome bd respiratory oxygen reductases. *Biochim Biophys Acta*. 2011; 1807(11):1398–1413. <https://doi.org/10.1016/j.bbabi.2011.06.016> PMID: 21756872
49. Leclerc J, Rosenfeld E, Trainini M, Martin B, Meuric V, Bonnaure-Mallet M, et al. The Cytochrome bd Oxidase of *Porphyromonas gingivalis* Contributes to Oxidative Stress Resistance and Dioxygen Tolerance. *PLoS ONE*. 2015; 10(12):e0143808. <https://doi.org/10.1371/journal.pone.0143808> PMID: 26629705
50. Gevrekci AO. The roles of polyamines in microorganisms. *World J Microbiol Biotechnol*. 2017; 33(11):204. <https://doi.org/10.1007/s11274-017-2370-y> PMID: 29080149
51. Mukhopadhyay A, He Z, Alm EJ, Arkin AP, Baidoo EE, Borglin SC, et al. Salt stress in *Desulfovibrio vulgaris* Hildenborough: an integrated genomics approach. *J Bacteriol*. 2006; 188(11):4068–4078. <https://doi.org/10.1128/JB.01921-05> PMID: 16707698
52. Lefevre CT, Bernadac A, Yu-Zhang K, Pradel N, Wu LF. Isolation and characterization of a magnetotactic bacterial culture from the Mediterranean Sea. *Environ Microbiol*. 2009; 11(7):1646–1657. <https://doi.org/10.1111/j.1462-2920.2009.01887.x> PMID: 19220399
53. Silva KT, Abreu F, Keim CN, Farina M, Lins U. Ultrastructure and cytochemistry of lipid granules in the many-celled magnetotactic prokaryote, ‘*Candidatus Magnetoglobus multicellularis*’. *Micron*. 2008; 39(8):1387–1392.
54. Zhou K, Zhang WY, Pan HM, Li JH, Yue HD, Xiao T, et al. Adaptation of spherical multicellular magnetotactic prokaryotes to the geochemically variable habitat of an intertidal zone. *Environ Microbiol*. 2013; 15(5):1595–1605. <https://doi.org/10.1111/1462-2920.12057> PMID: 23279048
55. Schwartzman JA, Ebrahimi A, Chadwick G, Sato Y, Roller BRK, Orphan VJ, et al. Bacterial growth in multicellular aggregates leads to the emergence of complex life cycles. *Curr Biol*. 2022; 32(14):3059–69 e7. <https://doi.org/10.1016/j.cub.2022.06.011> PMID: 35777363
56. Gulli JG, Herron MD, Ratcliff WC. Evolution of altruistic cooperation among nascent multicellular organisms. *Evolution*. 2019; 73(5):1012–1024. <https://doi.org/10.1111/evo.13727> PMID: 30941746
57. Jurenas D, Fraikin N, Goormaghtigh F, Van Melderen L. Biology and evolution of bacterial toxin-antitoxin systems. *Nat Rev Microbiol*. 2022; 20(6):335–350. <https://doi.org/10.1038/s41579-021-00661-1> PMID: 34975154
58. Keim CN, Abreu F, Lins U, de Barros HL, Farina M. Cell organization and ultrastructure of a magnetotactic multicellular organism. *J Struct Biol*. 2004; 145(3):254–262. <https://doi.org/10.1016/j.jsb.2003.10.022> PMID: 14960376
59. Serra DO, Hengge R. Bacterial Multicellularity: The Biology of *Escherichia coli* Building Large-Scale Biofilm Communities. *Ann Rev Microbiol*. 2021; 75:269–290. <https://doi.org/10.1146/annurev-micro-031921-055801> PMID: 34343018
60. Wrótniak-Drzewiecka W, Brzezińska AJ, Dahm H, Ingle AP, Rai M. Current trends in myxobacteria research. *Ann Microbiol*. 2015; 66(1):17–33.
61. Bi Y, Hubbard C, Purushotham P, Zimmer J. Insights into the structure and function of membrane-integrated processive glycosyltransferases. *Curr Opin Struct Biol*. 2015; 34:78–86. <https://doi.org/10.1016/j.sbi.2015.07.008> PMID: 26342143
62. McNamara JT, Morgan JL, Zimmer J. A molecular description of cellulose biosynthesis. *Annu Rev Biochem*. 2015; 84:895–921. <https://doi.org/10.1146/annurev-biochem-060614-033930> PMID: 26034894
63. Serra DO, Hengge R. Cellulose in bacterial biofilms. 2019.
64. Serra DO, Richter AM, Hengge R. Cellulose as an architectural element in spatially structured *Escherichia coli* biofilms. *J Bacteriol*. 2013; 195(24):5540–5554. <https://doi.org/10.1128/JB.00946-13> PMID: 24097954
65. Islam ST, Vergara Alvarez I, Saidi F, Guiseppi A, Vinogradov E, Sharma G, et al. Modulation of bacterial multicellularity via spatio-specific polysaccharide secretion. *PLoS Biol*. 2020; 18(6):e3000728. <https://doi.org/10.1371/journal.pbio.3000728> PMID: 32516311
66. Omadjela O, Narahari A, Strumillo J, Melida H, Mazur O, Bulone V, et al. BcsA and BcsB form the catalytically active core of bacterial cellulose synthase sufficient for in vitro cellulose synthesis. *Proc Natl*



- Acad Sci U S A. 2013; 110(44):17856–17861. <https://doi.org/10.1073/pnas.1314063110> PMID: 24127606
67. Qi Y, Rao F, Luo Z, Liang ZX. A flavin cofactor-binding PAS domain regulates c-di-GMP synthesis in AxDGC2 from *Acetobacter xylinum*. *Biochemistry*. 2009; 48(43):10275–10285. <https://doi.org/10.1021/bi901121w> PMID: 19785462
  68. Serra DO, Conover MS, Arnal L, Sloan GP, Rodriguez ME, Yantorno OM, et al. FHA-mediated cell-substrate and cell-cell adhesions are critical for *Bordetella pertussis* biofilm formation on abiotic surfaces and in the mouse nose and the trachea. *PLoS ONE*. 2011; 6(12):e28811. <https://doi.org/10.1371/journal.pone.0028811> PMID: 22216115
  69. Prasad SM, Yin Y, Rodzinski E, Tuomanen EI, Masure HR. Identification of a carbohydrate recognition domain in filamentous hemagglutinin from *Bordetella pertussis*. *Infect Immun*. 1993; 61(7):2780–2785. <https://doi.org/10.1128/iai.61.7.2780-2785.1993> PMID: 8514379
  70. Namba A, Mano N, Takano H, Beppu T, Ueda K, Hirose H. OmpA is an adhesion factor of *Aeromonas veronii*, an optimistic pathogen that habituates in carp intestinal tract. *J Appl Microbiol*. 2008; 105(5):1441–1451. <https://doi.org/10.1111/j.1365-2672.2008.03883.x> PMID: 18828791
  71. Maier B, Wong GCL. How Bacteria Use Type IV Pili Machinery on Surfaces. *Trends Microbiol*. 2015; 23(12):775–788. <https://doi.org/10.1016/j.tim.2015.09.002> PMID: 26497940
  72. Craig L, Forest KT, Maier B. Type IV pili: dynamics, biophysics and functional consequences. *Nat Rev Microbiol*. 2019; 17(7):429–440. <https://doi.org/10.1038/s41579-019-0195-4> PMID: 30988511
  73. Simmons SL, Sievert SM, Frankel RB, Bazylinski DA, Edwards KJ. Spatiotemporal distribution of marine magnetotactic bacteria in a seasonally stratified coastal salt pond. *Appl Environ Microbiol*. 2004; 70(10):6230–6239. <https://doi.org/10.1128/AEM.70.10.6230-6239.2004> PMID: 15466570
  74. Sobrinho RL, Lins U, Bernardes MC. Geochemical Characteristics Related to the Gregite-Producing Multicellular Magnetotactic Prokaryote *Candidatus Magnetoglobus multicellularis* in a Hypersaline Lagoon. *Geomicrobiol J*. 2011; 28(8):705–713.
  75. Berry D, Mader E, Lee TK, Woebken D, Wang Y, Zhu D, et al. Tracking heavy water (D<sub>2</sub>O) incorporation for identifying and sorting active microbial cells. *Proc Natl Acad Sci U S A*. 2015; 112(2):E194–E203. <https://doi.org/10.1073/pnas.1420406112> PMID: 25550518
  76. Tan L, Jiang J. Digital signal processing: fundamentals and applications: Academic press; 2018.
  77. Popa R, Weber PK, Pett-Ridge J, Finzi JA, Fallon SJ, Hutcheon ID, et al. Carbon and nitrogen fixation and metabolite exchange in and between individual cells of *Anabaena oscillarioides*. *ISME J*. 2007; 1(4):354–360. <https://doi.org/10.1038/ismej.2007.44> PMID: 18043646
  78. Herrero A, Stavans J, Flores E. The multicellular nature of filamentous heterocyst-forming cyanobacteria. *FEMS Microbiol Rev*. 2016; 40(6):831–854. <https://doi.org/10.1093/femsre/fuw029> PMID: 28204529
  79. Hu D, Cui Y, Markillie LM, Chrisler WB, Wang Q, Hatzenpichler R, et al. Counting mRNA Copies in Intact Bacterial Cells by Fluctuation Localization Imaging-Based Fluorescence In Situ Hybridization (fli-FISH). *Methods Mol Biol*. 2021; 2246:237–247. [https://doi.org/10.1007/978-1-0716-1115-9\\_15](https://doi.org/10.1007/978-1-0716-1115-9_15) PMID: 33576993
  80. Dar D, Dar N, Cai L, Newman DK. Spatial transcriptomics of planktonic and sessile bacterial populations at single-cell resolution. *Science*. 2021; 373(6556). <https://doi.org/10.1126/science.abi4882> PMID: 34385369
  81. Geier B, Sogin EM, Michellod D, Janda M, Kompauer M, Spengler B, et al. Spatial metabolomics of in situ host-microbe interactions at the micrometre scale. *Nat Microbiol*. 2020; 5(3):498–510. <https://doi.org/10.1038/s41564-019-0664-6> PMID: 32015496
  82. Stepanauskas R, Fergusson EA, Brown J, Poulton NJ, Tupper B, Labonte JM, et al. Improved genome recovery and integrated cell-size analyses of individual uncultured microbial cells and viral particles. *Nat Commun*. 2017; 8(1):84. <https://doi.org/10.1038/s41467-017-00128-z> PMID: 28729688
  83. Rinke C, Lee J, Nath N, Goudeau D, Thompson B, Poulton N, et al. Obtaining genomes from uncultivated environmental microorganisms using FACS-based single-cell genomics. *Nat Protoc*. 2014; 9(5):1038–1048. <https://doi.org/10.1038/nprot.2014.067> PMID: 24722403
  84. Chen IA, Chu K, Palaniappan K, Ratner A, Huang J, Huntemann M, et al. The IMG/M data management and analysis system v. 7: content updates and new features. *Nucleic Acids Res*. 2023; 51(D1):D723–D732. <https://doi.org/10.1093/nar/gkac976> PMID: 36382399
  85. Kang DD, Li F, Kirton E, Thomas A, Egan R, An H, et al. MetaBAT 2: an adaptive binning algorithm for robust and efficient genome reconstruction from metagenome assemblies. *PeerJ*. 2019; 7:e7359. <https://doi.org/10.7717/peerj.7359> PMID: 31388474

86. Parks DH, Imelfort M, Skennerton CT, Hugenholtz P, Tyson GW. CheckM: assessing the quality of microbial genomes recovered from isolates, single cells, and metagenomes. *Genome Res.* 2015; 25(7):1043–1055. <https://doi.org/10.1101/gr.186072.114> PMID: 25977477
87. Hyatt D, Chen G-L, LoCascio PF, Land ML, Larimer FW, Hauser LJ. Prodigal: prokaryotic gene recognition and translation initiation site identification. *BMC Bioinformatics.* 2010; 11:1–11.
88. Jain C, Rodriguez RL, Phillippy AM, Konstantinidis KT, Aluru S. High throughput ANI analysis of 90K prokaryotic genomes reveals clear species boundaries. *Nat Commun.* 2018; 9(1):5114. <https://doi.org/10.1038/s41467-018-07641-9> PMID: 30504855
89. Van Dongen S. Graph clustering via a discrete uncoupling process. *SIAM J Matrix Anal Appl.* 2008; 30(1):121–141.
90. Bushnell B. BBMap: a fast, accurate, splice-aware aligner. Lawrence Berkeley National Lab. 2014.
91. Schaible GA, Kohtz AJ, Cliff J, Hatzenpichler R. Correlative SIP-FISH-Raman-SEM-NanoSIMS links identity, morphology, biochemistry, and physiology of environmental microbes. *ISME. Communications.* 2022; 2(1). <https://doi.org/10.1038/s43705-022-00134-3> PMID: 37938730
92. Hatzenpichler R, Orphan VJ. Detection of Protein-Synthesizing Microorganisms in the Environment via Bioorthogonal Noncanonical Amino Acid Tagging (BONCAT). *Hydrocarbon and Lipid Microbiology Protocols. Springer Protocols Handbooks.* 2015. p. 145–57.
93. Tang G, Peng L, Baldwin PR, Mann DS, Jiang W, Rees I, et al. EMAN2: an extensible image processing suite for electron microscopy. *J Struct Biol.* 2007; 157(1):38–46. <https://doi.org/10.1016/j.jsb.2006.05.009> PMID: 16859925