



Behavior of the reconstructed Wolf Creek culvert
by Gerald Anson Willett

A thesis submitted to the Graduate Faculty in partial fulfillment of the requirements for the degree of
MASTER OF SCIENCE in Civil Engineering
Montana State University
© Copyright by Gerald Anson Willett (1967)

Abstract:

The failure of an 18.5 foot diameter structural-plate culvert under 83 feet of cover led to its reconstruction using the "imperfect trench" type of construction as well as other changes. This paper reports the findings of a research project that was initiated to study the behavior of the reconstructed culvert. The study was sponsored by the Montana State Highway Commission and the Bureau of Public Roads and was performed by the Department of Civil Engineering and Engineering Mechanics at Montana State University.

The reconstructed culvert was instrumented to study its behavior. Instrumentation consisted of: SR-4 strain gages placed on the culvert walls at approximately mid-height; Carlson Soil Stress Meters, placed on the outside walls of the culvert and in the fill; rubber pressure cells, which were commercial hot water bottles, placed in the fill; and settlement cells, which were placed in the fill on each side of the culvert. Also, measurements that were taken included: levels on the culvert invert, vertical and horizontal diameters, and levels of the roadway profile.

Computer programs were developed to determine stresses and earth pressure from data obtained by periodic readings of the instruments.

Overall, the instrumentation performed satisfactorily. Results from strain gages, stress meters, and rubber pressure cells, correlated well and demonstrated that the vertical load on the culvert was much less than the weight of the overlying column of earth - a highly favorable load condition which the "imperfect trench" method of construction was expected to produce. The SR-4 strain gages, which measured bending strains in addition to circumferential compression, showed that significant residual bending stresses were induced in the plates during erection. They also monitored bending stress changes that occurred at the strain gage sites during and after the backfilling operation. The vigorous compaction of the backfill on each side of the culvert, during the early stages of backfilling, produced a bending stress pattern in the side walls that persisted throughout the embankment construction period and thereafter.

There was no measurable differential settlement of the pavement attributable to the "imperfect trench" type of construction.

240
1098B

BEHAVIOR OF THE RECONSTRUCTED
WOLF CREEK CULVERT

by

GERALD ANSON WILLETT, JR.

A thesis submitted to the Graduate Faculty in partial
fulfillment of the requirements for the degree


of

MASTER OF SCIENCE


in

Civil Engineering


Approved:



Head, Major Department



Chairman, Examining Committee



Dean, Graduate Division

MONTANA STATE UNIVERSITY

Bozeman, Montana

August, 1967

ACKNOWLEDGEMENTS

The Author wishes to show his appreciation by thanking those who have helped in making this thesis possible. Thanks go to the thesis committee, especially to Professor A. C. Scheer, Major Advisor for the Author.

The study and research for the Large Culvert Research Project was made possible by the Bureau of Public Roads and the Montana State Highway Commission, who sponsored the project, using Highway Planning and Research funds. Thanks go to the personnel of these agencies who assisted in the project.

The Author also wishes to thank employees of the Montana State Highway Department, Armco Steel Corporation, and F & S Construction Company for their fine cooperation in the field; and Leonard Grayson, technician for the Montana State University Civil Engineering Department, for his assistance with the instrumentation under the direction of Mr. Scheer.

TABLE OF CONTENTS

CHAPTER I	INTRODUCTION-----	1
CHAPTER II	BACKGROUND INFORMATION ON THE WOLF CREEK CULVERT-----	3
CHAPTER III	THEORY OF CULVERT LOADING AND THE IMPERFECT TRENCH-----	7
CHAPTER IV	SELECTION AND DESIGN OF INSTRUMENTATION-----	12
	GENERAL-----	12
	STRAIN GAGES-----	13
	PRESSURE CELLS-----	19
	SETTLEMENT CELLS-----	26
CHAPTER V	RECONSTRUCTION OF CULVERT AND INSTALLATION OF INSTRUMENTATION-----	29
	CULVERT RECONSTRUCTION-----	29
	STRAIN GAGE INSTALLATION-----	37
	PRESSURE CELL INSTALLATION-----	42
	SETTLEMENT CELL INSTALLATION-----	51
CHAPTER VI	READING INSTRUMENTS AND TAKING MEASUREMENTS-	53
CHAPTER VII	REDUCTION OF DATA-----	57
CHAPTER VIII	RESULTS AND ANALYSIS OF DATA-----	66
CHAPTER IX	DISCUSSION, CONCLUSIONS AND RECOMMENDA- TIONS-----	112

DISCUSSION-----	112
CONCLUSIONS-----	117
RECOMMENDATIONS-----	119
APPENDICES-----	121
APPENDIX A - COMPUTER PROGRAM FOR STRAIN	
GAGES-----	122
PARTIAL OUTPUT DATA FROM STRAIN GAGE	
COMPUTER PROGRAM-----	126
APPENDIX B - COMPUTER PROGRAM FOR STRESS	
METERS-----	137
PARTIAL OUTPUT DATA FROM STRESS METER	
COMPUTER PROGRAM-----	139
LITERATURE CITED-----	142

LIST OF FIGURES

FIGURE

1	PLAN AND PROFILE AT CULVERT SITE-----	4
2	TYPICAL CROSS-SECTION OF REBUILT CULVERT-----	10
3	FOIL STRAIN GAGE-----	14
4	POSITION OF SR-4 STRAIN GAGES TO MEASURE CIRCUM- FERENTIAL STRAIN IN THE CORRUGATED PLATES-----	17
5	BALDWIN-LIMA-HAMILTON TYPE N PORTABLE INDICATOR WITH COMPENSATING GAGES BEFORE WATERPROOFING-----	19
6	CARLSON SOIL STRESS METER-----	20
7	CARLSON STRESS METER CROSS-SECTION-----	23
8	CHECKING EFFECT OF SHEAR STRESSES ON STRESS METERS----	25
9	SETTLEMENT CELL AND MANOMETER BOARD DETAILS-----	27
10	STREAM DIVERSION DAM AND DIVERSION PIPES-----	30
11	TRENCHING FOR PERFORATED PIPE DRAIN-----	30
12	PIPE ERECTION-----	33
13	CONTROL DEVICE WITH STREAM FLOW THROUGH CULVERT----	33
14	WALKWAYS, CROSSWALKS AND FOLDING TABLES IN CULVERT-----	35
15	COMPACTING MATERIAL UNDER HAUNCH-----	35
16	BACKFILL MATERIAL PLACED IN SIX INCH LAYERS-----	36
17	PLACEMENT OF BALED STRAW FIVE FEET ABOVE CULVERT-----	36
18	MOUNTED STRAIN GAGES ON PLATE BEFORE ERECTION AND COMPENSATING GAGES-----	40

FIGURE

19	THREE STRAIN GAGES ON OUTSIDE OF PLATE AFTER ERECTION -----	40
20	ANGLE IRON PROTECTION FOR GAGES AGAINST THE FILL.--	41
21	COMPENSATING GAGES HANGING IN CULVERT BELOW MEASURING GAGES -----	41
22	LOCATION OF SR-4 STRAIN GAGES, SETTLEMENT CELLS AND CONTROL DEVICES -----	43
23	MOUNTING FRAMES FOR STRESS METERS INSTALLED ON CULVERT -----	44
24	MOUNTING FRAME WITH MORTAR BACKING -----	45
25	STRESS METER TEST SET AND SWITCHBOARD -----	45
26	STRESS METER INSTALLED WITH SAND PROTECTION -----	47
27	STRESS METER FROM THE INSIDE OF THE CULVERT -----	47
28	METERS IN FILL IN MOUNTING FRAMES PERPENDICULAR TO THE CULVERT CENTER LINE -----	48
29	LOCATION OF CARLSON STRESS METERS AND RUBBER PRESSURE CELLS -----	49
30	RUBBER PRESSURE CELLS PLACED IN FILL -----	50
31	BOURDON GAGES AND VALVES INSIDE CULVERT -----	50
32	SETTLEMENT CELL IN THE FILL -----	52
33	MANOMETER BOARD AND VALVES MOUNTED ON CONCRETE HEADWALL -----	52

FIGURE

34	DETERMINING EARTH PRESSURE FROM COMPRESSIVE FORCE IN WALLS-----	60
35	EARTH PRESSURES FROM INELASTIC STRAINS-----	62
36	DETERMINING TEMPERATURE AND EARTH PRESSURE FROM STRESS METER READINGS-----	65
37	ERECTION STRESSES IN THE SIX INSTRUMENTED PLATES-----	67
38	STRESSES CAUSED BY ERECTION AND EARTH PRESSURE-----	70
39	STRESSES CAUSED BY EARTH PRESSURE-----	71
40	STRESSES CAUSED BY THE ADDITIONAL 78 FEET OF COVER-----	76
41	COMBINED STRESSES ON 3 /25/66 and 3 /27/67-----	79
42	EQUIVALENT UNIFORM VERTICAL EARTH PRESSURES ON CULVERT, DEDUCED FROM SR-4 STRAIN GAGES-----	81
43	EARTH PRESSURE VS. TIME - STRESS METERS NO. 1, 6, 7, 11, 23, AND 24-----	83
44	EARTH PRESSURE VS. TIME - STRESS METERS NO. 19 AND 22-----	84
45	EARTH PRESSURE VS. TIME - STRESS METERS NO. 3, 4, 14, 15, 18 AND 20-----	85
46	EARTH PRESSURE VS. TIME - STRESS METERS NO. 2, 5, 13, 16, 17 AND 21-----	86

FIGURE

47	EARTH PRESSURE VS. TIME - STRESS METERS NO. 8, 10, AND 12-----	87
48	EARTH PRESSURE VS. TIME - STRESS METERS NO. 25, 26, 27, 28, 29 AND 30-----	88
49	EARTH PRESSURES ACTING ON THE CULVERT WALLS ON 1 / 4/66-----	91
50	EARTH PRESSURES ON 1 / 4/66 DETERMINED FROM THE STRESS METERS AND RUBBER PRESSURE CELLS LOCATED IN THE FILL-----	95
51	EARTH PRESSURE VS. TIME - RUBBER PRESSURE CELLS NO. 1, 2, 3, 4, 5 AND 6-----	98
52	SETTLEMENT OF THE SETTLEMENT CELLS AND TOP OF CULVERT-----	103
53	SETTLEMENT OF THE CULVERT INVERT-----	105
54	AVERAGE HORIZONTAL AND VERTICAL DIAMETER CHANGE-----	107
55	SETTLEMENT OF THE INTERSTATE ROADWAY PAVEMENT-----	111
56	PRESSURE ON TOP OF CULVERT DETERMINED FROM RUBBER PRESSURE CELLS-----	115

LIST OF TABLES

TABLE

1	STRESSES IN THE CHICAGO SUBWAY TUNNEL WALLS DETERMINED FROM PRESSURE CELLS AND STRAIN GAGES -----	21
2	STRESSES CAUSED BY ERECTION -----	68
3	STRESSES CAUSED BY ERECTION AND FIVE FEET OF COVER-----	72
4	STRESSES CAUSED BY FIVE FEET OF COVER -----	72
5	STRESSES CAUSED BY ERECTION AND 83 FEET OF COVER-----	73
6	STRESSES CAUSED BY 83 FEET OF COVER -----	73
7	STRESSES CAUSED BY THE ADDITIONAL 78 FEET OF COVER-----	77
8	SETTLEMENT OF THE SETTLEMENT CELLS IN INCHES-----	100
9	SETTLEMENT OF THE CULVERT INVERT -----	104
10	VERTICAL DIAMETER CHANGE-----	108
11	HORIZONTAL DIAMETER CHANGE-----	109

ABSTRACT

The failure of an 18.5 foot diameter structural-plate culvert under 83 feet of cover led to its reconstruction using the "imperfect trench" type of construction as well as other changes. This paper reports the findings of a research project that was initiated to study the behavior of the reconstructed culvert. The study was sponsored by the Montana State Highway Commission and the Bureau of Public Roads and was performed by the Department of Civil Engineering and Engineering Mechanics at Montana State University.

The reconstructed culvert was instrumented to study its behavior. Instrumentation consisted of: SR-4 strain gages placed on the culvert walls at approximately mid-height; Carlson Soil Stress Meters, placed on the outside walls of the culvert and in the fill; rubber pressure cells, which were commercial hot water bottles, placed in the fill; and settlement cells, which were placed in the fill on each side of the culvert. Also, measurements that were taken included: levels on the culvert invert, vertical and horizontal diameters, and levels of the roadway profile.

Computer programs were developed to determine stresses and earth pressures from data obtained by periodic readings of the instruments.

Overall, the instrumentation performed satisfactorily. Results from strain gages, stress meters, and rubber pressure cells, correlated well and demonstrated that the vertical load on the culvert was much less than the weight of the overlying column of earth - a highly favorable load condition which the "imperfect trench" method of construction was expected to produce.

The SR-4 strain gages, which measured bending strains in addition to circumferential compression, showed that significant residual bending stresses were induced in the plates during erection. They also monitored bending stress changes that occurred at the strain gage sites during and after the backfilling operation. The vigorous compaction of the backfill on each side of the culvert, during the early stages of backfilling, produced a bending stress pattern in the side walls that persisted throughout the embankment construction period and thereafter.

There was no measurable differential settlement of the pavement attributable to the "imperfect trench" type of construction.

CHAPTER I

INTRODUCTION

This paper describes the behavior of an 18.5 foot diameter structural-plate culvert that was reconstructed after the failure of the original structure. Construction of the original installation began in the fall of 1963. The rock fill, which provided approximately 83 feet of cover on the culvert, was completed in the spring of 1964. It was discovered that the structure had failed in the summer of 1964, within three months after the fill was completed, but it is not known exactly when the failure began.

Solutions for repairing the structure were reviewed and the final conclusion was to remove the fill and rebuild the failed portion of the culvert. Removal of the fill began that winter. Reconstruction of the culvert was delayed until the following fall, 1965, because of higher than normal runoff and the resulting problem of stream diversion.

Extensive testing by the culvert contractor was done to determine the cause of the failure. The test results indicated that the failure may have been caused by "hydrogen embrittlement" of the zinc-coated high strength bolts. It was thought by some of the engineers involved that the culvert loading may have been larger than anticipated; therefore, the reconstruction was designed for an increased margin of safety. In addition to changing the type and size of bolts, an "imperfect trench"

type of construction was used. It was decided that the culvert should be instrumented and that a study should be made on the behavior of the reconstructed culvert.

The design and installation of instrumentation, and the study of the behavior of the reconstructed structure was performed by the Department of Civil Engineering and Engineering Mechanics at Montana State University. The study was under the sponsorship of the Montana State Highway Commission and the Bureau of Public Roads.

CHAPTER II

BACKGROUND INFORMATION ON THE WOLF CREEK CULVERT

The culvert installation is located on Little Prickley Pear Creek near the south end of Wolf Creek Canyon on Interstate Route 15, about 25 miles north of Helena, Montana. The Interstate plan-profile at the culvert site is shown in Figure 1. The design details of the original culvert are covered in a paper by Kraft and Eagle (8)¹.

The culvert was 548 feet long. Corrugated and galvanized structural steel plates, 3/8 inch thick, were used in the middle 328 feet and thinner plates were used near the ends.

Design loading on the structure was 8.2 kips per square foot from 83 feet of fill having an assumed unit weight of 105 pounds per cubic foot. The use of 3/8 inch plate and 3/4 inch high strength bolts resulted in a design seam strength of 270,000 pounds per linear foot and provided an apparent safety factor of 3.5. The high strength bolts used with the 3/8 inch plates of the original culvert were zinc-coated ASTM A490 bolts while the remaining bolts used with the thinner plates, were zinc-coated ASTM A325 bolts. Because the original structure was not instrumented, the actual load on the structure could not be determined.

The failure was due to "brittle-like" fracture of the bolts along the longitudinal seams of the lower half of the culvert. The failure

¹Numbers in parentheses refer to references listed under Literature Cited.

